93431

F.AID. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8183	04-00120-00-FP	MORGAN	28	10
STA. 492+50	TO STA. 498+50			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SEC 30, T15N, R10W, 3RD PM

SEC 29, T15N, R10W, 3RD PM

DG PROPERTIES, INC

STONEBRIDGE APARTMENTS, LP

APARTMENT OFFICE #1225

BALSAM TERRACE VOLUNTEERS OF AMERICA ELDERLY HOUSING

INLET (TY B W/ MEDIAN
INLET STD 604106), 34.31' LT
STA 493+20
T.G. 609.32
INV. 606.15

INV. 606.35

INLET (B-3V), W/ FST
20.00' LT, STA 493+20
T.C. 610.60
INV. 605.95

INLET (TY A W/ TY 1 FRAME,
CLOSED LID)
STA 493+90.7, 34.00' LT
LID 610.00
INV. 606.70

CL SURVEY & CONSTRUCTION
LINCOLN AVENUE (FAU 8183)

PROPOSED 5' SIDEWALK

PROPOSED B-6.24 COMBINATION CONCRETE CURB AND GUTTER

LINCOLN AVENUE

MATCH LINE STA 492+50

M.H. NO. 6
STA 493+20
T.C. 610.60

M.H. NO. 7
STA 495+45
T.C. 607.64

M.H. NO. 8
STA 496+02
T.C. 606.90

CONNECT SS WMR TO EXISTING 12" PVC

INV. 600.80

INV. 602.40

INV. 603.30

INV. 605.65

INV. 606.05

PROPOSED 5' SIDEWALK

M.H. NO. 9 (EXIST)
STA 497+03

INV. 598.24

SECTION 04-00120-00-FP ENDS
STA 496+59.55

EXISTING O&C SURFACE

ROUTT COLLEGE FARM NO. 7

RP LUMBER CO., INC

STA 492+50.00
40.00' RT

STA 492+50.00
55.00' RT

STA 492+84.20
55.00' RT

STA 492+84.20
40.00' RT

JACKSONVILLE AREA COUNCIL ON ALCOHOLISM

HENRY B. POOLE & DORIS J. POOLE

WELLS CENTER, INC

JAMES L. BUCK & LUCILLE N. BUCK

EIGHT WHEELER, INC

KERASOTES SHOWPLACE THEATRES, LLC

SUPERIOR AVENUE

LINCOLN AVENUE

PROPOSED TEMPORARY EASEMENT LINE

STA 495+67.85
30.00' RT

STA 495+67.84
40.00' RT

STA 495+90.83
40.00' RT

STA 495+90.83
30.00' RT

STA 496+65.85
30.00' RT

PROPOSED ROW LINE
STA 496+75.84
40.00' RT

PT STA 497+05.56
N - 1111763.39 E - 2273687.29
MAG NAIL

BM #10

SCALE IN FEET

BM #10 - TOP OF NE FLNG. BLT. F. HYD. @ NE CORNER OF LINCOLN AVE. & SUPERIOR STREET
STA. 497+55.96, 27.70' RT.
ELEVATION = 604.79

PROFILE

EXISTING GROUND LINE (CL SURVEY)

PROPOSED PROFILE GRADE LINE

SP DT LT 1.40%

-1.31%

18" S.S. @ 1.00%

24" S.S. @ 0.50%

24" S.S. @ 1.00%

24" S.S. @ 1.00%

30" S.S.

M.H. NO. 6, STA 493+20.00, 20.00' RT (A-3V), 5' DIA., F.S.T. STD 602601, T.C. = 610.60

M.H. NO. 7, STA 495+45.00, 20.00' RT (A-3V), 5' DIA., F.S.T. STD 602601, T.C. = 607.64

M.H. NO. 8, STA 496+02.00, 20.00' LT (A-3V), 5' DIA., F.S.T. STD 602601, T.C. = 606.90

M.H. NO. 9 (EXIST), STA 497+03.00, 20.00' LT

INV. 606.70

INV. 605.65

INV. 604.43

INV. 603.30

INV. 603.10

INV. 602.40

INV. 600.80

INV. 599.25

INV. 598.24

	492+50	493+00	493+50	494+00	494+50	495+00	495+50	496+00	496+50	497+00	497+50	498+00
(EXISTING)	611.60	610.71	609.86	609.22	608.63	608.24	607.86	606.98	606.18	605.49	605.10	604.47
(PROPOSED)	611.42	610.77	610.11	609.46	608.80	608.14	607.49	606.83	606.18	606.05		

+59.95

LINCOLN AVENUE (FAU 8183), STA 492+50 TO STA 498+50

PLAN: SURVEYED, PLOTTED, DESIGNED, CHECKED, QUANTITIES CHECKED, NOTE BOOK, NO. ____, BY, DATE

PROFILE: SURVEYED, PLOTTED, DESIGNED, CHECKED, QUANTITIES CHECKED, NOTE BOOK, NO. ____, BY, DATE, ALL NOTED STRUCTURE NOTATIONS CHKD

V:\237\237435.dgn 01/16/2007 08:54:39 AM