F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	29
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

PHILPOT MACHINE & TOOL, LTD.

DEBRA CARROLL, D/B/A THE DEPOT OF VANDALIA, ILLINOIS

STA 4+62.80
44.09 LT

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

PORTLAND CEMENT CONCRETE SIDEWALK, 4" (TYPICAL)

STA 4+46.76
43.82 LT

TEMP CONST. EASEMENT

TEMP CONST. EASEMENT

CE STA 5+50.87

STA 6+14.73
46.65 LT

8"-.001in

EXIST ROW

STA 605+52

B SIXTH STREET

DENNIS GRUBAUGH AND DEBORAH GRUBAUGH

TIM METZGER

LEWIS E. CLYMER AND ARLENE CLYMER

COMMUNITY OPPORTUNITIES, IN

ROBERT ANDERSON

NEDRA M. HAYNES AND CARROLL J. HAYNES

PORTLAND CEMENT CONCRETE SIDEWALK, 4" (TYPICAL)

STA 4+55.74 =
STA 6704+44.04
ST.

℄ GALLATIN STREET

STA 6+55.79=
STA 604+40.67

STA 8+56.85 =
STA 5604+40.67

GALLATIN ST.

COMBINATION CONCRETE CURB AND GUTTER B-6.18 (TYPICAL)

MATCH LINE STA 4+00

MATCH LINE STA 10+00

91°17'24.51"

89°40'33"

91°17'24"

89°42'46"

STA 4+67.80

STA 4+79.47

STA 6+13.61

STA 7+01.89

SEE HANDICAP RAMP DETAIL

EXIST ROW

CE STA 5+88.20

TEMP CONST. EASEMENT

PORTLAND CEMENT CONCRETE SIDEWALK, 4" (TYPICAL)

STA 4+48.91
54.16 RT

THE FIRST BAPTIST CHURCH OF VANDALIA, ILLINOIS

THE FIRST BAPTIST CHURCH OF VANDALIA, ILLINOIS

TRAVERSE STATION #431213
NORTHING = 99935.446
EASTING = 98980.236
ELEV = 506.399
STA 603+61.78

KENNETH A. WILLIAMS AND PEGGY L. WILLIAMS

VOID UNDER SIDEWALK TO BE FILLED WITH CLSM

FRED A. METZGER OR LUCILLE M. METZGER, TRUSTEE(S)

MATTHEW E. LABERTEW AND

JOHN R. MABRY AND VIRGINIA E. MABRY

DENNIS GRUBAUGH AND DEBORAH GRUBAUGH

DENNIS GRUBAUGH AND DEBORAH GRUBAUGH

SANJAY AGARWAL AND RAVI AGARWAL

VOID UNDER SIDEWALK TO BE FILLED WITH CLSM

DUANE GARD, THOMAS MICHAEL DORAN, KIM HACKETT AND KAROLYN BOYER

SCALE IN FEET
0 20 40

LEGEND

- 5' BRICK CIRCULAR PATTERN
- 3' BRICK SIDEWALK
- RED OR WHITE DOGWOOD TREE WITH GUARD AND GRATE
- 4' BLACK BENCH WITH BACK
- 22 GALLON BLACK TRASH CAN
- VINTAGE STREET LIGHT ON ORNAMENTAL POLE
- DETECTABLE WARNINGS
- EROSION CONTROL BLANKET

PROFILE

125.00' V.C.

50.00' V.C.

50.00' V.C.

30.00' V.C.

-9.41%

-2.00%

-2.00%

-1.40%

-1.40%

-2.21%

-2.21%

+0.99%

VPI STA. 4+22.10
ELEVATION 510.26

VPI STA. 5+20.69
ELEVATION 508.29

VPI STA. 6+46.93
ELEVATION 506.52

VPI STA. 6+93.64
ELEVATION 505.49

PROPOSED PROFILE ALONG ℄

EXISTING PROFILE ALONG ℄

525 520 515 510 505 500 495 490 485

4+00	4+50	5+00	5+50	6+00	6+50	7+00	7+50	8+00	8+50	9+00	9+50	10+00
512.75 / 512.82	511.45 / 511.54	510.42 / 510.49	509.67 / 509.68	509.11 / 509.11	508.68 / 508.70	508.30 / 508.34	507.88 / 508.02	507.45 / 507.74	507.04 / 507.46	506.64 / 507.18	506.44 / 506.90	506.58 / 506.61	506.22 / 506.23	505.75 / 505.83	505.61 / 505.66	505.69 / 505.75	505.87 / 505.95	506.06 / 506.14	506.23 / 506.34	506.43 / 506.54	506.68 / 506.74	506.93 / 506.93	507.07 / 507.13	507.29 / 507.33	507.52 / 507.53	507.75 / 507.72	507.97 / 507.92	508.11 / 508.12	508.25 / 508.31	508.43 / 508.51

CADD FILE: 14812/pp_Gallatin_02.dgn
PLOTTED: 3/12/2007

H.M. & G. NO. 14812