

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00016-02-RP	MADISON	42	2
STA.	TO STA.			
CONTRACT NO.: 97290				

INDEX OF SHEETS

SHEET NO.	SHEET TITLE
1	COVER SHEET
2	INDEX OF SHEETS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	EXISTING & PROPOSED TYPICAL SECTIONS
5-7	ALIGNMENT, TIES, AND BENCHMARKS
8-10	SCHEDULE OF QUANTITIES
11-13	PLAN & PROFILE WEST CORBIN STREET
14-16	TRAFFIC CONTROL
17-19	EROSION AND SEDIMENT CONTROL PLANS
20	EROSION AND SEDIMENT CONTROL DETAILS
21-22	DRAINAGE AND UTILITIES PLAN
23	DRIVEWAY AND ENTRANCE DETAILS
24-26	INTERSECTION DETAILS
27	PAVEMENT MARKINGS
28	PAVED DITCH DETAILS
29	MISCELLANEOUS DETAILS
30	STORM SEWER PROFILES
	DISTRICT DETAILS
31-38	CROSS SECTIONS-WEST CORBIN STREET
39	CROSS SECTIONS-MILES DRIVE
40	CROSS SECTIONS-WEST DRIVE
41-42	CROSS SECTIONS-SCHOOL DRIVEWAY

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STANDARD NO.	STANDARD TITLE
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT REBARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-03	TEMPORARY EROSION CONTROL SYSTEMS
424001-04	CURB RAMPS FOR SIDEWALKS
542301-01	PRECAST REINFORCED CONCRETE FLARED END SECTION
542311	GRATING FOR CONCRETE FLARED END SECTION (FOR 600mm THRU 1350mm (54") PIPE)
602301-01	INLET - TYPE A
602308-01	INLET - TYPE B
602401-01	MANHOLE TYPE A
602701-01	CAST IRON STEPS
604001-02	FRAME AND LIDS TYPE 1
604008-02	FRAME AND GRATE TYPE 3
604011-02	FRAME AND GRATE TYPE 3V
604091-01	FRAME AND GRATE TYPE 24
606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606401	PAVED DITCH
635008-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
701001-01	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701501-01	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
702001-06	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720008-01	SIGN PANEL ERECTION DETAILS
720011	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
729001	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)
780001-01	TYPICAL PAVEMENT MARKINGS
B.L.R. 10-5	PCC PAVEMENT SPECIAL
B.L.R. 17-3	TRAFFIC CONTROL DEVICES - DAY LABOR CONSTRUCTION
B.L.R. 21-6	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

LEGEND

	EXISTING SHRUB
	EXISTING LIGHT POLE
	EXISTING GUY WIRE
	EXISTING CLEANOUT

ABBREVIATIONS AND SYMBOLS

TBR&R TO BE REMOVED AND REPLACED

GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
 - CONTRACTOR TO VERIFY 6" HIGH PRESSURE GAS LINE ELEVATION AND LOCATION PRIOR TO EARTHWORK, INSTALLATION, AND ORDERING AND ACCEPTANCE OF ANY MATERIALS.
 - THE CONTRACTOR SHALL PROTECT UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE FOLLOWING UTILITIES ARE LOCATED WITHIN THE LIMITS OF THIS PROJECT:
 - AMEREN IP (GAS)
1050 WEST BLVD.
BELLEVILLE, ILLINOIS 62221
(800) 755-5000
 - AMEREN IP (ELECTRIC)
1050 WEST BLVD.
BELLEVILLE, ILLINOIS 62221
(800) 755-5000
 - VILLAGE OF BETHALTO (SEWER)
101 SOUTH PRAIRIE ST.
BETHALTO, IL 62010
(618) 377-8723
 - SBC AMERITECH (TELEPHONE)
203 GOETHE ST.
COLLINSVILLE, ILLINOIS 62234
(618) 346-6490
 - VILLAGE OF BETHALTO (WATER)
101 SOUTH PRAIRIE ST.
BETHALTO, IL 62010
(618) 377-8723
 - CHARTER COMMUNICATIONS (CABLE)
210 DIVISION ST.
MARYVILLE, IL 62062
(888) 438-2427
- JULIE
1-800-892-0123
- IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN SUBMITTING HIS BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCES CAUSED BY THE SAME.
- THE INFORMATION AND DATA SHOWN OR INDICATED ON THESE IMPROVEMENT PLANS WITH RESPECT TO EXISTING UNDERGROUND FACILITIES AND UTILITIES AT OR CONTIGUOUS TO THE SITE IS BASED ON INFORMATION AND DATA FURNISHED BY THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES OR BY OTHERS. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE TO THE RESIDENT ENGINEER SO THAT UTILITIES CAN BE GIVEN NOTICE. NO GUARANTEE IS IMPLIED AS TO THE ACCURACY OR COMPLETENESS OF ANY SUCH INFORMATION OR DATA; AND CONTRACTOR SHALL HAVE FULL RESPONSIBILITY FOR (i) REVIEWING AND CHECKING ALL SUCH INFORMATION AND DATA, (ii) LOCATING ALL UNDERGROUND FACILITIES AND UTILITIES SHOWN OR INDICATED ON THE IMPROVEMENT PLANS; (iii) COORDINATION OF THE WORK WITH THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (iv) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES AND REPAIR ANY DAMAGE THERETO RESULTING FROM THE WORK AT HIS EXPENSE.
- ALL UTILITIES TO BE RELOCATED BY OTHERS.
 - THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
 - ALL AREAS DISTURBED FOR ANY REASON SHALL BE SEEDING WITH CLASS 1B SEEDING, AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
 - MULCH, AS APPLIED TO FINAL SEEDING (CLASS 1B), SHALL CONFORM TO SECTION 251 OF THE STANDARD SPECIFICATIONS. MULCH UNLESS OTHERWISE PERMITTED BY THE ENGINEER, SHALL CONFORM TO METHOD 2 AS SPECIFIED IN ARTICLE 251.03 (b).
 - ALL WORK AS SHOWN ON THESE PLANS SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIAL PROVISIONS PREPARED BY HOELSCHER ENGINEERING, P.C. ENTITLED "FAU ROUTE 8959 (WEST CORBIN STREET) SECTION 05-00016-02-RP, CONTRACT NO. 97290, VILLAGE OF BETHALTO".
 - SEE STANDARD BLR-10 FOR DETAILS OF JOINTS AND REBARS NOT SHOWN ON THE PLANS.
 - SUBGRADE IS TO BE COMPACTED AND SHALL CONFORM TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 (REFER TO SECTION 300).
 - PROTECTIVE COAT SHALL BE APPLIED TO ALL PAVEMENT, GUTTER FLAGS AND FACE OF CURBS ACCORDING TO THE SEASONAL REQUIREMENT OF ARTICLE 420.18 OF THE STANDARD SPECIFICATIONS.
 - FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF SIXTEEN SANDBAGS PER BARRICADE
 - ALL ROAD CLOSED BARRICADES SHALL HAVE FLASHING LIGHTS.
 - THE CONTRACTOR FOR THIS PROJECT SHALL PERFORM HIS WORK IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 105.08 "COOPERATION BETWEEN CONTRACTORS" OF THE STANDARD SPECIFICATIONS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR FOLLOWING THE REQUIREMENTS OF AN NPDES STORM WATER PERMIT FOR CONSTRUCTION ACTIVITY FOR THIS PROJECT.
 - CONCRETE REMOVAL (50102400) IS ASSUMED TO BE 6" THICK.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX OF SHEETS, STANDARDS AND
GENERAL NOTES

FAP ROUTE
SECTION 05-00016-02-RP
COUNTY MADISON

DRAWN BY: R.A.W.