

# SUMMARY OF QUANTITIES

MAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-0016-02-RP	MADISON	42	3
STA.		TO STA.		
CONTRACT NO.: 97290				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		5000-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	90			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	90			
20200100	EARTH EXCAVATION	CU YD	3,317			
20900210	POROUS GRANULAR BACKFILL, SPECIAL	CU YD	201			
25000115	SEEDING, CLASS 1B	ACRE	0.70			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63			
25100115	MULCH, METHOD 2	ACRE	0.70			
28000300	TEMPORARY DITCH CHECKS	EACH	3			
28000500	INLET AND PIPE PROTECTION	EACH	14			
28000900	FENCE (EROSION CONTROL)	FOOT	471			
30200650	PROCESSING MODIFIED SOIL, 12"	SQ YD	5,343			
30201500	LIME	TON	104			
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	4,510			
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	127			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	239			
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH, 10")	SQ YD	637			
42000311	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2"(JOINTED)	SQ YD	3,782			
42001300	PROTECTIVE COAT	SQ YD	5,460			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	895			
42303400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	179			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	8,717			
42400800	DETECTABLE WARNINGS	SQ FT	375			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,150			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	61			
44000600	SIDEWALK REMOVAL	SQ FT	656			
44004000	PAVED DITCH REMOVAL	FOOT	32			
50102400	CONCRETE REMOVAL	CU YD	1			
50104605	CONCRETE RETAINING WALL REMOVAL	CU YD	1			
50105220	PIPE CULVERT REMOVAL	FOOT	359			
50901765	PIPE HANDRAIL, SPECIAL	FOOT	57			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	124			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	353			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	287			
550B0060	STORM SEWERS, CLASS B, TYPE 1 14"	FOOT	54			
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	135			
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1			
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1			
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1			
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1			
60242500	INLETS, SPECIAL, NO. 1	EACH	2			
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	4			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12	FOOT	94			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.24	FOOT	2,534			

NOTE: \* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		5000-2A		
60617525	PAVED DITCH, TYPE B-37 SPECIAL	FOOT	37			
67100100	MOBILIZATION	LUMP SUM	1			
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	LUMP SUM	1			
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	62			
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,461			
*78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	273			
*78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	66			
X2800500	INLET PROTECTION, SPECIAL	EACH	2			
X5420350	END SECTIONS 18" SPECIAL	EACH	2			
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	2			
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	2			
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	442			
XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	255			
XX001607	RETAINING WALL, SPECIAL	SQ FT	18			

SUMMARY OF QUANTITIES