FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
	05-00016-02-RP	MADISON	42	13
STA. 21+50	TO STA. 27+00			
CONTRACT NO.: 97290				

PLAN
SURVEYED BY: ACC DATE: 2/2/06
PLOTTED BY: ACC DATE: 2/2/06
NOTE BOOK: ____ NO. ____
CHECKED: E.R.O.
FINAL CHECKED: E.R.O.
R/W CHECKED: E.R.O.
ENG. NOTED: E.R.O.
CADD FILE NAME: 05984DVERALL

PROFILE
SURVEYED BY: ACC DATE: 2/2/06
PLOTTED BY: ACC DATE:
NOTE BOOK: ____ NO. ____
FINAL CHECKED: E.R.O.
R/W CHECKED:
ENG. NOTED:
STRUCTURE NOTATNS CHKD

N

20' 0 20' 40'
GRAPHIC SCALE

NOTE: ALL ENTRANCES AT 90° TO MAINLINE UNLESS OTHERWISE NOTED

BENCHMARK DATUM
BM2 NAIL IN POWER POLE
WEST CORBIN STREET
STA. 20+90.82, 32.30 RIGHT

PROPOSED TEMPORARY CONSTRUCTION EASEMENT
EXISTING TEMPORARY CONSTRUCTION EASEMENT
EX GI TOP 493.24 E 489.08
EX GI TOP 489.67 E 485.47
℄ STADIUM DRIVE
EX GI TOP 493.24 E 489.24
INLET NO. 515
EX AI TOP 498.00 E 482.38
EX GI TOP 492.25 E 482.38
18"
18"
15"
PCC SIDEWALK
EXISTING TEMPORARY GRADING EASEMENT
n/f CHRISTOPHER DEPEW (4192/1258)
n/f JEFFERY MOSS (4353/3125)
+59.76, 20' CONC. P.E.
+91.46, 12' CONC. P.E.
4'
24+00
23+00
22+00
25' R.O.W.
13'
13'
25' R.O.W.
4'
EX GI TOP 492.61 E 482.39
+44.85, 12' CONC. P.E.
EXISTING TEMPORARY GRADING EASEMENT
EX GI TOP 489.48 E 482.15
STA. 23+72.63
WEST CORBIN STREET =
STA. 13+09.32
STADIUM DRIVE
INLET NO. 510
EXISTING END OF PIPE, CONTRACTOR TO VERIFY LOCATION AND ELEVATION PRIOR TO ORDERING AND INSTALLING MATERIALS
STATION 23+04.74
TRANSITION TO MATCH EXISTING
STA. 23+10.97
END PCC PAVEMENT
AND COMB CC&G
TB6.24
PCC PAVEMENT
PCC SIDEWALK
CC&G
TB6.24 (TYP)
n/f DAVID REDMAN (4095/1615)
n/f DAVID REDMAN (4095/1615)

NOTE:
CONTRACTOR TO VERIFY 6" HIGH PRESSURE GAS LINE ELEVATION AND LOCATION PRIOR TO ORDERING, CONSTRUCTION AND INSTALLATION OF MATERIALS AND EXCAVATION

MATCH LINE, STATION 21+50

515
510
505
500
495
490
485
480

250' VC
PVI STA = 21+77.58
PVI ELEV = 495.91
A.D. = 1.59
K = 157.12

STA. 23+10.97
END PAVEMENT
EVCS: 23+02.58
EVCE: 492.90
EXISTING AGG SURF CSE (TBR)
PROPOSED P.G.L.
2.41%
EXISTING TELEPHONE LINE
PROPOSED 12" RCP
INV. 488.54
EXISTING 6" HIGH PRESSURE GAS LINE
EXISTING STORM SEWER

490.6 491.75
491.3 492.36
493.0 492.96
493.2 493.59
494.5 494.25
493.9 494.96
494.2 495.70
495.0 496.49
495.8 497.32
497.1 498.18

23+50 23+00 22+50 22+00 21+50

MATCH LINE, STATION 21+50

SCALE
HORIZ. 1"=20'
VERT. 1"=5'

PLAN & PROFILE-WEST CORBIN STREET, STA. 21+50 TO 23+10.97