

REMOVAL SCHEDULE

LOCATION	REMOVE EXISTING STRUCTURE (EACH)	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNITS)
	50100100	20100110
STA 447+63.19 TO STA 448+36.86	1	
STA 447+50.00, 60.00' LT TO STA 448+50.00, 60.00' LT		72
STA 449+73.44, 35.87' RT TO STA 450+07.43, 36.21' RT		
TOTAL	1	72

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (ACRE)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (TON)
	25000200	25000400	25000400	25000600	25100120
STA 446+00 LT TO STA 447+82 LT	0.10	9.0	9.0	9.0	0.2
STA 446+00 RT TO STA 447+82 RT	0.10	9.0	9.0	9.0	0.2
STA 448+15 LT TO STA 450+00 LT	0.15	13.5	13.5	13.5	0.3
STA 448+15 RT TO STA 450+50 RT	0.15	13.5	13.5	13.5	0.3
TOTAL	0.5	45.0	45.0	45.0	1.0

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING (LB)	PERIMETER EROSION BARRIER (FOOT)	TEMPORARY DITCH CHECKS (EACH)	EROSION CONTROL BLANKET (SQ YD)
	28000250	28000400	28000300	25100630
STA 446+00 LT TO STA 447+82 LT	10			
STA 446+00 RT TO STA 447+82 RT	10			
STA 446+00 LT TO STA 447+00 LT		100		
STA 446+00 RT TO STA 447+50 RT		150		
STA 448+15 LT TO STA 450+00 LT	15			
STA 448+50 RT TO STA 450+50 RT	15			
STA 448+30 LT TO STA 450+00 LT				170
STA 448+30 RT TO STA 449+74 RT				144
STA 448+50 LT			1	
STA 448+50 RT			1	
STA 449+50 LT			1	
STA 449+50 RT			1	
STA 450+00 RT TO STA 450+50 RT		50		
TOTAL	50	300	4	314