

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

• FAI 57 & FAU 9629 (OLD IL 13)
 ** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON										
LOCATION:	URBAN										
ROUTE:	F. A. I. 57										
FUNDING:	90% FEDERAL/ 10% STATE - ACIM						FAU 9629 (OLD IL 13)				
WORK TYPE:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY	
	STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB 157 RAMP ACIM	VA & NB 157 RAMP ACIM	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM	

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE:																		
				I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A									
28100205	STONE RIPRAP, CLASS A3	TON	366.0	366.0																		
28100207	STONE RIPRAP, CLASS A4	TON	74.0																			74.0
28200200	FILTER FABRIC	SQ YD	428.0	428.0																		
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	22,003.0	17,134.0																		4,869.0
30201500	LIME	TON	655	509																		144.0
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	762.0																			762.0
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	514.0																			514.0
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1998	1998																		
31200500	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4"	SQ YD	4051	4051																		
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	392.0																			392.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34,988	30,994																		1,674.0
40600300	AGGREGATE (PRIME COAT)	TON	80.5	51.7																		28.8
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3.0																			3.0
40600895	CONSTRUCTING TEST STRIP	EACH	3.0	3.0																		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3414	3034																		380.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	187.0																			187.0
40600990	TEMPORARY RAMP	SQ YD	1,586.0	1,417.0																		169.0
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	29,441	28,913																		528.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	11,759	10,184																		1,575.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1,535.0																			1,535.0
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	3,205.0	3,205.0																		
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	5331	5331																		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACE	TON	144.0																			144.0

PLOT DATE = 12/14/2006
 FILE NAME = c:\pco\pco\pco\192282\add13\add13.spl.m32
 PLOT SCALE = 50.0000 / IN.
 USER NAME = pco\pco

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

3 OF 13

SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY JCK CHECKED BY

REV. 2-26-07