CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	COUNTY:	WILLIAMSON									
				LOCATION:	URBAN									
				ROUTE:	F.A.I. 57						FAU 9629 (OLD IL 13)			
				FUNDING:	90% FEDERAL/ 10 % STATE-ACIM						90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY
				WORK TYPE:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
					STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB I57 RAMPS ACIM	VA & NB I57 RAMPS	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
		CONSTRUCTION TYPE CODE:			I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1.0		1.0									
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	5.0		5.0									
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	2.0		2.0									
54215472	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 72"	EACH	2.0		2.0									
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	2.0		2.0									
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	1.0		1.0									
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	3.0		2.0								1.0	
54248510	CONCRETE COLLAR	CU YD	11.8		11.0								0.8	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,741.0		1,436.0								305.0	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	572.0		563.0								9.0	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	1,007.0		757.0								250.0	
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	280.0		280.0									
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	441.0		36.0								405.0	
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	93.0										93.0	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	336.0										336.0	
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	62.0										62.0	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	72.0		35.0								37.0	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	73.0										73.0	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	26.0		26.0									
55100500	STORM SEWER REMOVAL 12"	FOOT	33.0										33.0	
55100700	STORM SEWER REMOVAL 15"	FOOT	12.0										12.0	
55100900	STORM SEWER REMOVAL 18"	FOOT	171.0										171.0	
55101200	STORM SEWER REMOVAL 24"	FOOT	538.0		52.0								486.0	
55101400	STORM SEWER REMOVAL 30"	FOOT	314.0										314.0	
55101900	STORM SEWER REMOVAL 48"	FOOT	134.0										134.0	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	449.0			208.0	241.0							
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	22.0		22.0									
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	90.0		90.0									
60107600	PIPE UNDERDRAINS 4"	FOOT	26,360.0		26,360.0									
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1,882.0		1,882.0									
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	744.0			374.0	370.0							

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
7 OF 12

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/14/2005
FILE NAME = c:\projects\d9928282\std\d97std13asheh.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjo