CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

			COUNTY:	WILLIAMSON								
			LOCATION:	URBAN								
			ROUTE:	F.A.I. 57						FAU 9629 (OLD IL 13)		
			FUNDING:	90% FEDERAL/ 10 % STATE- *ACIM*						90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY
			WORK TYPE:	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB I57 RAMPS *ACIM*	VA & NB I57 RAMPS	STA. 753+20 TO STA. 784+40 *ACIM*	STA. 753+20 TO STA. 784+40 *ACIM*
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE: I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	2.0							2.0			
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2.0							2.0			
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1.0								1.0		
87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	1.0							1.0			
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	2.0							1.0	1.0		
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	2.0								2.0		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6.0							6.0			
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	6.0							3.0	3.0		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20.0							10.0	10.0		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56.0							13.0	43.0		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3.0							1.0	2.0		
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	9.0							3.0	6.0		
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1.0							1.0			
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3.0							1.0	2.0		
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4.0							2.0	2.0		
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2.0								2.0		
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2.0							2.0			
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	12.0							4.0	8.0		
88500100	INDUCTIVE LOOP DETECTOR	EACH	16.0							6.0	10.0		
88500200	INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT	EACH	9.0							3.0	6.0		
88600100	DETECTOR LOOP, TYPE 1	FOOT	3,000.0							825.0	2,175.0		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2.0							2.0			
~~X0006231~~	~~BRIDGE DECK HYDRO-SCARIFICATION 3 1/2"~~	~~SQ YD~~	~~1,945.0~~				~~1,945.0~~						
X0325683	STABILIZED SUB-BASE - HOT-MIX ASPHALT (VARIABLE DEPTH)	TON	9,365.0	9,365.0									
X0325684	CORING FOR GUARDRAIL INSTALLATION	FOOT	400.0	400.0									
52100540	ANCHOR BOLTS, 1 1/2"	EACH	46.0		46.0								
X0325685	SUB-BASE GRANULAR MATERIAL, 6"	SQ YD	37,426.0	37,426.0									
X0325686	SUB-BASE GRANULAR MATERIAL, 10"	SQ YD	1,722.0	1,722.0									

~~Q Y080~~
* SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
12 OF 12

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/14/2006
FILE NAME = c:\projects\sm82882\xldl3\xldl3schun32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjb