CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	29
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

PIPE CULVERTS

LOCATION	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL EQUIVALENT ROUND-SIZE			PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE			TRENCH BACKFILL	PIPE CULVERTS, CLASS A,									PRECAST REINFORCED CONCRETE FLARED END SECTIONS		CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS				CONCRETE COLLAR
								TYPE 1	TYPE 2		TYPE 3			TYPE 4		TYPE 5								
	18"	27"	60"	18"	27"	60"		21"	24"	36"	36"	48"	72"	30"	48"	72"	21"	24"	30"	36"	48"	72"	
	FOOT	FOOT	FOOT	EACH	EACH	EACH	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	CU YD
FAI 57																							
NORTHBOUND																							
LT STA 1508+64															25						1		0.93
LT STA 1514+59													12									1	1.55
LT STA 1537+62										27										1			0.66
LT STA 1545+16										12										1			0.66
SOUTHBOUND																							
RT STA 1507+14												15									1		0.93
RT STA 1513+58																30						1	1.55
RT STA 1539+61										25										1			0.66
RT STA 1546+74										24										1			0.66
RAMP E																							
RT STA 1+80.6									34									1					
LT STA 1+80.6									46									1					
RAMP EE																							
RT STA 11+71														60					1				0.56
RAMP F																							
RT STA 14+50									60									1					
LT STA 10+81.48									6														0.58
LT STA 14+50																		1					
RAMP FF																							
RT STA 5+12											40									1			0.66
FAI 57 PROJECT TOTALS	0	0	0	0	0	0	0.0	0	146	88	40	15	12	60	25	30	0	4	1	5	2	2	9.4
FAU 9629 (OLD IL 13)																							
LT. STA. 755+15 TO STA. 756+25	108.5																						
LT. STA. 756+25 TO STA. 756+75	48.5																						
LT. STA. 756+75				1																			
RT. STA. 761+53					1																		
RT. STA. 761+53.4 TO STA. 761+85		26																					
RT. STA. 761+85 TO STA. 762+24.4													38										
RT. STA. 762+24																		1					
RT. STA. 771+72										1													
RT. STA. 771+76 TO STA. 773+71			200				144.0																
FAU 9629 (OLD IL 13) PROJECT TOTALS	157	26	200	1	1	1	144	38	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0.0
SCHEDULE PROJECT SUB-TOTALS	157	26	200	1	1	1	144	38	146	88	40	15	12	60	25	30	1	4	1	5	2	2	9.4
FROM STORM SEWER SCHEDULE							2,088.0										5	1					2.4
FROM BOX CULVERT SCHEDULE							163.0																
FROM DRAINAGE REMOVAL SCHEDULE							1,112.0																
PROJECT TOTALS	157	26	200	1	1	1	3,507	38	146	88	40	15	12	60	25	30	6	5	1	5	2	2	11.8

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = o:\projects\fas2382\old13\old13schum32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranje