

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	53

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

POLYUREA PAVEMENT MARKINGS

LOCATION STATION TO STATION	POLYUREA PAVEMENT MARKING TYPE II -						LETTERS AND SYMBOLS SQ FT		
	LINE 4"		LINE 6"		LINE 12"			LINE 24"	
	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT			
FAI 57									
NORTHBOUND									
STA 1515+63.11 TO STA 1517+56.11	50	193.00	193.00						
STA 1528+80.23 TO STA 1531+14.23	60	234.00	234.00						
SOUTHBOUND									
STA 1515+61.02 TO STA 1517+54.02	50	193.00	193.00						
STA 1528+78 TO STA 1531+12	60	234.00	234.00						
RAMP E									
STA. 0+68 STOP BAR						18			
STA. 0+34 TO STA. 0+88 PAINTED MEDIAN		170			63				
STA. 0+34 TO STA. 0+76		96							
STA. 0+76 TO STA. 3+46		274	275						
RAMP EE									
STA. 19+48 STOP BAR						12			
STA. 19+57 STOP BAR						13			
STA. 19+81 STOP BAR						18			
STA. 19+28 TO STA. 19+92 PAINTED MEDIAN					130				
STA. 17+58 ONLY (2 EA)							41.6		
STA. 18+03 ONLY							20.8		
STA. 17+86 TURN ARROW							15.6		
STA. 18+31 TURN ARROW							15.6		
STA. 17+86 THRU ARROW							11.5		
STA. 16+69.69 TO STA. 17+48		80	78						
STA. 17+48 TO STA. 17+93		135	45						
STA. 17+93 TO STA. 19+60		281	157						
STA. 19+28 TO STA. 19+92		216							
STA. 17+93 TO STA. 19+92		324							
RAMP F									
STA. 13+60.5 ONLY							41.6		
STA. 13+88.5 TURN ARROW							31.2		
STA. 15+48 STOP BAR						19			
STA. 15+63 STOP BAR						18			
STA. 15+20 TO STA. 15+84 PAINTED MEDIAN					136				
STA. 12+62 TO STA. 13+40		168	78						
STA. 13+40 TO STA. 15+20		360	180						
STA. 15+20 TO STA. 15+49		96	29						
STA. 15+49 TO STA. 15+82		263	9						
RAMP FF									
STA. 0+34 TO STA. 2+00		218							
STA. 0+61 TO STA. 3+37.79			278						
STA. 2+00 TO STA. 3+37.79		138							
STA. 0+70 STOP BAR						18			
STA. 0+34 TO STA. 0+89 PAINTED MEDIAN		172			70				
FAI 57 PROJECT SUBTOTALS									
	220	3,845	1,983	0	399	116	178		
FAI 57 PROJECT TOTALS									
	6,048			0	399	116	178		
FAU 9629 (OLD IL 13)									
CRISP DR.									
STA. 10+47						15			
STA. 10+75				48					
FAU 9629 (OLD IL 13) PROJECT TOTALS									
	0	0	0	48	0	15	0		
FAU 9629 (OLD IL 13) PROJECT TOTALS									
	0			48	0	15	0		
PROJECT TOTALS									
	6,048			48	399	131	178		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE
		SCALE: VERT. DRAWN BY JCK
		HORIZ. CHECKED BY
		DATE

PLOT DATE = 12/11/2006
 FILE NAME = c:\pvc\mca\d982882\old\3\old\3aehm32
 PLOT SCALE = 80.0000' / IN.
 USER NAME = kranzlj