

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

## CONCRETE BARRIER

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

LOCATION STATION TO STATION	CONCRETE BARRIER, DOUBLE FACE 42 INCH HEIGHT	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PROTECTIVE COAT	REMARKS
	FOOT	FOOT	FOOT	SQ YD	
FAI 57					
PRE-STAGE 1					
NORTHBOUND					
LT STA 1489+62 TO STA 1493+37		375.0			
SOUTHBOUND					
RT STA 1488+53 TO STA 1492+16		362.5			
PRE-STAGE 2					
NORTHBOUND					
RT STA 1489+68 TO STA 1493+06			337.5		RELOCATE FROM PRESTAGE 1
RT STA 1493+06 TO STA 1493+68		62.5			
SOUTHBOUND					
LT STA 1488+20 TO STA 1492+20			400.0		RELOCATE FROM PRESTAGE 1
PRE-STAGE 3					
SOUTHBOUND					
RT STA 1526+52 TO STA 1530+77			425.0		RELOCATE FROM PRESTAGE 2
PRE-STAGE 4					
SOUTHBOUND					
RT STA 1528+14 TO STA 1530+77			262.5		RELOCATE FROM PRESTAGE 3
STAGE 1A	0.0	8,575.0	800.0	0.0	
STAGE 2	0.0	0.0	1,600.0	0.0	
STAGE 3	0.0	0.0	4,537.5	0.0	
STAGE 4	0.0	0.0	5,987.5	0.0	
STAGE 5	0.0	0.0	738.0	0.0	
STAGE 6	0.0	0.0	240.0	0.0	
STAGE 7	2,406.0	0.0	6,675.0	2,810.0	
STAGE 7C	710.0	0.0	1,901.0	993.0	
STAGE 8	0.0	0.0	88.0	0.0	
FAI 57 PROJECT TOTALS	3,116.0	9,375.0	23,992.0	3,803.0	
OLD IL 13					
LT STA 765+17.5 TO STA 768+62.5		375.0			
FAU 9629 (OLD IL 13) PROJECT TOTALS	0.0	375.0	0.0	0.0	
SCHEDULE PROJECT SUB-TOTALS	3,116.0	9,750.0	23,992.0	3,803.0	
FROM CONCRETE CURB & GUTTER SCHEDULE				2,415.0	
FROM CONCRETE PAVEMENT SCHEDULE				7,898.0	
FROM SIDEWALK SCHEDULE				1,188.0	
PROJECT TOTALS	3,116.0	9,750.0	23,992.0	15,304.0	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p><b>SCHEDULE</b></p> <p>SCALE: VERT.      DRAWN BY JCK                      HORIZ.              CHECKED BY                      DATE</p>

PLOT DATE = 1/19/2007  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = hrcn2jps