

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	64

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)WB-2, (X1-6)HBK-2

SIGNS

LOCATION STATION TO STATION	OFFSET FROM EDGE OF PAVEMENT TO FIRST POST	SIGN ID NO.	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 3	CONCRETE FOUNDATIONS CU YD	DRILLED SHAFT CONCRETE FOUNDATIONS CU YD	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY		CONCRETE FOUNDATION, GROUND MOUNT CU YD	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' - 0" X 4' - 6") FOOT	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5' - 6") FOOT	OVERHEAD SIGN WALKWAY, TYPE A FOOT	OVERHEAD SIGN WALKWAY, CANTILEVER, TYPE A FOOT	REMARKS
			SQ FT	SQ FT			POST SIZE (INFO. ONLY)	POUND						
FAI 57														
NORTHBOUND														
STA 1532+00														
STA 1532+00	PROPOSED OVERHEAD SPAN	9S1001057L52.8			17.2	14.8				80.0		57.0		FOUNDATION IN MEDIAN MUST BE DONE IN I-57 STAGE 7
STA 1532+00	CARBONDALE IL 13 WEST			174.0										SIGN PANEL-TYPE 3 IS PAID 100% STATE
STA 1532+00	MARION HARRISBURG IL 13 EAST			217.5										SIGN PANEL-TYPE 3 IS PAID 100% STATE
STA 1532+00	MAIN ST. MARION			117.0										SIGN PANEL-TYPE 3 IS PAID 100% STATE
LT STA 1535+00	VA MEDICAL CENTER	36.7		72.0			W6 X 15	562.5	1.4					
LT STA 1545+50	MAIN ST. MARION	32.5		131.3			W10 X 26	1,307.8	2.4					
SOUTHBOUND														
STA 1515+50	PROPOSED CANTILEVER MAIN ST. MARION	9C1001057R53.1		117.0		6.9					30.0		14.0	SIGN PANEL-TYPE 3 IS PAID 100% STATE
RAMP EE														
RT STA 11+50	CAMPING	22.0		47.5			W6 X 15	595.5	1.4					
RT STA 13+00	GAS	21.2		76.0			W8 X 18	822.6	1.4					
RT STA 14+50	LODGING	18.5		100.0			W8 X 18	801.0	1.4					
RT STA 16+00	FOOD	18.5		100.0			W8 X 18	765.0	1.4					
RT STA 17+50	VA MEDICAL CENTER, MARION, CRAG ORCHARD LAKE	18.2		110.0			W8 X 18	768.6	1.4					
RAMP F														
RT STA 8+00	CAMPING	21.5		47.5			W6 X 15	594.0	1.4					
RT STA 9+50	GAS	21.5		76.0			W6 X 15	610.5	1.4					
RT STA 11+50	LODGING	24.2		100.0			W8 X 18	810.0	1.4					
RT STA 13+00	FOOD	22.5		100.0			W8 X 18	756.0	1.4					
RT STA 14+40	VA MEDICAL CENTER, MARION, CRAG ORCHARD LAKE	31.0		110.0			W10 X 22	1,174.8	1.4					SIGN STRADDLES DITCH
FAI 57 PROJECT TOTALS:				0	1695.8	17.2	21.7	9568.3	17.8	80	30	57	14	
FAU 9629 (OLD IL 13)														
RT STA 761+50	157 NORTH MT. VERNON, 157 SOUTH CAIRO	26.2		132.0			W8 X 18	788.4	1.4					
LT STA 763+25	157 SOUTH CAIRO	27.2		63.0			W6 X 15	504.0	1.4					
RT STA 771+50	157 NORTH MT. VERNON	17.1		75.0			W6 X 15	585.0	1.4					SIGN STRADDLES DITCH
RT STA 771+77	W MAIN STREET MAST ARM		9.0											
LT STA 772+67	W MAIN STREET MAST ARM		9.0											
LT STA 773+50	157 SOUTH CAIRO, 157 NORTH MT. VERNON	18.9		155.3			W10 X 26	1,333.8	2.4					
FAU 9629 (OLD IL 13) PROJECT TOTALS:				18	425.3	0	0	3211.2	6.6	0	0	0	0	
PROJECT TOTALS:				18.0	2,121.1	17.2	21.7	12,779.5	24.4	80.0	30.0	57.0	14.0	

ALL SIGN NOTED AS 100% STATE SHALL USE THE SPECIAL PROVISION FOR TYPE ZZ RETROREFLECTIVE SHEETING AND TRANSLUCENT OVERLAY FILM FOR HIGHWAY SIGNS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/13/2006
FILE NAME = c:\p\projects\98950\13\old\3\sh-m32
SCALE = 5/8" = 1' / IN.
USER NAME = kcrn25