

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	146
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
 ** (X1-6-2IVB-2, (X1-6)HBK-2

SHOULDERS - FAI 57 STAGE 1

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS, SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	AGGREGATE SHOULDERS, TYPE A	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	TON	6 1/2" SQ YD	8" SQ YD	8 1/2" SQ YD	9 1/2" SQ YD	8" SQ YD	TON	GALLON	FOOT	
FAI 57											
NORTHBOUND											
RT (INSIDE SHOULDER)											
STA. 1542+33 TO STA. 1550+25	528						176				
STA. 1550+25 TO STA. 1551+75	100						33				
SOUTHBOUND											
RT (OUTSIDE SHOULDER)											
STA. 1500+00 TO STA. 1504+00	460						69				STOP AT GORE AREA - STA 1503+10
STA. 1502+10 TO STA. 1504+00	173			42.0							
STA. 1504+00 TO STA. 1509+43.5 BK	497			120.0							
STA. 1509+15.58 AH TO STA. 1510+00	79			19.0							
LT (INSIDE SHOULDER)											
STA. 1542+33 TO STA. 1550+25	528						176				
STA. 1550+25 TO STA. 1556+85	440						147				
FAI 57 STAGE 1 PROJECT TOTALS	2,805.0	0.0	0.0	181.0	0.0	0.0	601.0	0.0	0.0	0.0	

PLT DATE : 10/25/2006
 FILE NAME : c:\p022822\old\13\old\13shou32
 PLOT SCALE : 50.0000' / IN.
 USER NAME : kranzje

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE

SCALE: VERT. _____
 HORIZ. _____

DATE: _____

DRAWN BY JCK
 CHECKED BY _____