

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| * | ** | WILLIAMSON | 917 | 168 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HKB-2

EARTHWORK - FAI 57 STAGE 1A

| LOCATION STA TO STA | EARTH EXCAVATION CU YD | FOR INFORMATION ONLY | | | | | | REMARKS | |
|----------------------------------------------|------------------------------|-------------------------------------|--------------------------------------------|---------------------|----------------------|-----------------------|--------------------------------|----------------------------------------------------------------------------|-------------------------------|
| | | AVERAGE SHRINKAGE FACTOR % | EARTH EXCAVATION (ADJUSTED) CU YD | EMBANKMENT CU YD | EARTHWORK BALANCE | | BORROW SWELL FACTOR % | | BORROW EXCAVATION CU YD |
| | | | | | WASTE (+) CU YD | SHORTAGE (-) CU YD | | | |
| FAI 57 | | | | | | | | | |
| STA 1499+70 TO STA 1542+33 MEDIAN | 1,321 | 23.3% | 1,014 | 4,088 | -3,074 | | | | |
| STA 1519+99 TO STA 1542+51 MEDIAN UNSUITABLE | 4,276 | 0.0% | 4,276 | 0 | | | | SOIL TO BE DRIED OUT AND PLACED IN FAI 57 STAGE 3 - SEE SPECIAL PROVISIONS | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| FAI 57 STAGE 1A PROJECT TOTAL | 5,597 | 11.7% | 5,290 | 4,088 | -3,074 | 25.0% | 3,843 | | |

PLOT DATE = 1/16/2007
 PLOT SCALE = 50.0000' / IN.
 USER NAME = jrcnzg

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|-------------------------------------------------------------------------|
| NAME | DATE | |
| | | SCHEDULE SCALE: VERT. _____ HORIZ. _____ DATE _____ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

DRAWN BY JCK
CHECKED BY