CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	169
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EROSION CONTROL - FAI 57 STAGE 1A

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
FAI 57										
NORTHBOUND										
RT STA 1490+79 TO STA 1515+56										
RT STA 1506+76								1.0		
RT STA 1509+00							1.0			
RT STA 1511+50							1.0			
RT STA 1517+63 TO STA 1528+73										
RT STA 1517+98								1.0		
RT STA 1520+00							1.0			
RT STA 1523+00							1.0			
RT STA 1526+00							1.0			
RT STA 1531+22 TO STA 1542+33										
RT STA 1538+70								1.0		
RT STA 1540+25							1.0			
RT STA 1542+33							1.0			
FAI 57 STAGE 1A PROJECT TOTAL	0.0	0.0	0.0	0.0	0.0	0.0	7.0	3.0	0.0	

SEEDING - FAI 57 STAGE 1A

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
NORTHBOUND								
RT STA 1506+94 TO STA 1513+00	25	0.25	0.25	40	30	30	0.5	0.50
RT STA 1513+00 TO STA 1515+83	4	0.04	0.04	6	5	5	0.1	0.08
RT STA 1520+00 TO STA 1528+73	33	0.33	0.33	53	40	40	0.7	0.66
RT STA 1530+70 TO STA 1536+50	7	0.07	0.07	11	8	8	0.1	0.14
RT STA 1536+50 TO STA 1542+00	21	0.21	0.21	34	25	25	0.4	0.42
SOUTHBOUND								
LT STA 1500+00 TO STA 1507+20	6	0.06	0.06	10	7	7	0.1	0.12
LT STA 1513+30 TO STA 1515+81	3	0.03	0.03	5	4	4	0.1	0.06
LT STA 1530+70 TO STA 1536+50	6	0.06	0.06	10	7	7	0.1	0.12
FAI 57 STAGE 1A PROJECT TOTALS	105	1.05	1.05	169	126	126	2.1	2.10

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\projects\vR92002\sld13\sld13eah.s2
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramzjo