CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	170
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 1A

LOCATION STATION TO STATION					PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING										SHORT TERM PAVEMENT MARKING	
					LINE 4"			LINE 4"				LINE 6"	LINE 8"		LINE 12"		LINE 24"	LETTERS AND SYMBOLS	
					SKIP-DASH WHITE	SOLID WHITE	SOLID YELLOW	SKIP-DASH WHITE	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE		WHITE	YELLOW
					FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
FAI 57																				
NORTHBOUND																				
STA.	1506+05	TO	STA.	1506+90	NOTE 3				85		85									
STA.	1506+90	TO	STA.	1507+81				23			91									
STA.	1507+81	TO	STA.	1510+48.26 BK				67	268		268									
STA.	1510+49.47 AH	TO	STA.	1510+95				12	46		46									
STA.	1510+95	TO	STA.	1518+78				196			783									
STA.	1517+30	TO	STA.	1518+78	ON RAMP E			37												
STA.	1518+78	TO	STA.	1526+85				202	807		807									
STA.	1526+85	TO	STA.	1530+71				97			386									
STA.	1530+71	TO	STA.	1542+33				291	1,162		1162									
STA.	1542+33	TO	STA.	1543+18	SEE NOTE 2				170		85									
SOUTHBOUND																				
STA.	1499+15	TO	STA.	1500+00	SEE NOTE 2				170		85									
STA.	1500+00	TO	STA.	1504+00				100	400		400									
STA.	1503+10	TO	STA.	1504+00	ON RAMP C SEE NOTE 1				90					90						
STA.	1504+00	TO	STA.	1506+10.5	ON RAMP C			53	211											
STA.	1504+00	TO	STA.	1506+10.5				53			211									
STA.	1506+10.5	TO	STA.	1509+43.5 BK				84	333		333									
STA.	1509+15.58 AH	TO	STA.	1517+34				205	819		819									
STA.	1517+34	TO	STA.	1519+37				51			203									
STA.	1519+37	TO	STA.	1526+25				172	688		688									
STA.	1526+25	TO	STA.	1527+90	ON RAMP FF			42												
STA.	1526+25	TO	STA.	1535+56				233			931									
STA.	1535+56	TO	STA.	1542+33				170	677		677									
STA.	1542+33	TO	STA.	1543+18	SEE NOTE 2				170		85									
FAI 57 STAGE 1A PROJECT SUBTOTALS						0	0	0	2,088	6,096	0	8,145	0	0	90	0	0	0	0	0	0
FAI 57 STAGE 1A PROJECT TOTALS						0			16,329				0	90		0		0	0	0

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.
2.) THE CENTERLINE AND THE RT. EDGELINE ARE SOLID WHITE.
3.) THE CENTERLINE IS SOLID WHITE.

PLOT DATE = 1/15/2007
FILE NAME = c:\projects\vb98280\sht\vb98280_sht03sch.dgn
PLOT SCALE = 50.0000 '/ IN.
USER NAME = krenzJC

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY