CONTRACT NO. 98950

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| * | ** | WILLIAMSON | 917 | 226 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

# SEEDING - FAI 57 STAGE 3

| LOCATION STATION TO STATION | TEMPORARY EROSION CONTROL SEEDING | SEEDING, CLASS 1B | SEEDING, CLASS 7 | NITROGEN FERTILIZER NUTRIENT | PHOSPHORUS FERTILIZER NUTRIENT | POTASSIUM FERTILIZER NUTRIENT | AGRICULTURAL GROUND LIMESTONE | MULCH, METHOD 2 |
|---|---|---|---|---|---|---|---|---|
| | POUND | ACRE | ACRE | POUND | POUND | POUND | TON | ACRE |
| FAI 57 | | | | | | | | |
| NORTHBOUND | | | | | | | | |
| LT STA 1506+90 TO STA 1513+00 | 89 | 0.89 | 0.89 | 142 | 107 | 107 | 1.8 | 1.78 |
| LT STA 1538+90 TO STA 1550+25 | 154 | 1.54 | 1.54 | 246 | 185 | 185 | 3.1 | 3.08 |
| SOUTHBOUND | | | | | | | | |
| RT STA 1536+00 TO STA 1544+50 | 101 | | 1.01 | 40 | | | | 1.01 |
| RT STA 1536+00 TO STA 1556+00 | 151 | 1.51 | 1.51 | 242 | 181 | 181 | 3.0 | 3.02 |
| FAI 57 STAGE 3 PROJECT TOTALS | 495 | 3.94 | 4.95 | 670 | 473 | 473 | 7.9 | 8.89 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\projects\d9825827\old37\old13sch.m32
PLOT SCALE = 50.0000 / IN.
USER NAME = kranzjo