

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	314
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HKB-2

EARTHWORK - FAI 57 STAGE 4

LOCATION STA TO STA	EARTH EXCAVATION CU YD	FOR INFORMATION ONLY					BORROW SWELL FACTOR %	BORROW EXCAVATION CU YD	REMARKS
		AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD				
FAI 57									
STA 1510+00 TO STA 1538+90	641	15.7%	540	39,238	-38,698				
STA 1529+09 TO STA 1530+83 BRIDGE CONE	1,167	16.5%	974	605	369				
STA 1515+92 TO STA 1517+25 BRIDGE CONE	0	15.4%	0	2,941	-2,941				
FAI 57 STAGE 4 PROJECT TOTAL	1,808	15.9%	1,514	42,784	-41,270	25.0%	51,588		

PLOT DATE = 1/16/2007
 FILE NAME = c:\pwworkspace\982822\d13\13\13ebw32
 PLOT SCALE = 0.0000 / IN.
 USER NAME = krenzjg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY