

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	WILLIAMSON	917	319
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

TEMPORARY PAVEMENT MARKINGS - FAI 57 STAGE 4

LOCATION STATION TO STATION	PAVEMENT MARKING TAPE, TYPE I I I (SPECIAL)			TEMPORARY PAINT PAVEMENT MARKING										SHORT TERM PAVEMENT MARKING		
	LINE 4"			LINE 4"				LINE 6"	LINE 8"		LINE 12"		LINE 24"	LETTERS AND SYMBOLS	PAVEMENT MARKING	
	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP-DASH WHITE FOOT	SOLID WHITE FOOT	SKIP-DASH YELLOW FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SQ FT	WHITE FOOT	YELLOW FOOT
FAI 57																
NORTHBOUND																
STA. 1506+90 TO STA. 1510+48.26 BK							90	358								358
STA. 1510+49.47 AH TO STA. 1523+45							320	1,296								1103
STA. 1523+45 TO STA. 1524+26 SEE NOTE 2								603								81
STA. 1524+26 TO STA. 1524+85							20	70								59
STA. 1524+85 TO STA. 1525+86							30	107								101
STA. 1525+86 TO STA. 1538+90							330	1,304								1304
STA. 1538+90 TO STA. 1540+00 SEE NOTE 2								220								110
STA. 1540+00 TO STA. 1550+00							250	1,000								1000
SOUTHBOUND																
STA. 1501+60 TO STA. 1503+00 SEE NOTE 2								374								160
STA. 1503+00 TO STA. 1503+17 SEE NOTE 2							10	61								22
STA. 1503+17 TO STA. 1505+90 SEE NOTE 2							70	819								273
STA. 1505+90 TO STA. 1509+43.5 BK							90	355								354
STA. 1509+15.58 AH TO STA. 1510+00							20	84								84
STA. 1510+00 TO STA. 1519+25							230	925								732
STA. 1519+25 TO STA. 1521+55 SEE NOTE 2							60	481								230
STA. 1521+55 TO STA. 1522+15 SEE NOTE 2								196								60
STA. 1522+15 TO STA. 1530+27							200	812								812
STA. 1530+27 TO STA. 1536+00 SEE NOTE 2							140	1201								595
STA. 1536+00 TO STA. 1537+10								220								110
STA. 1537+10 TO STA. 1545+05 I-57 AND TEMP FF							200	1590								1590
STA. 1545+05 TO STA. 1547+30 SEE NOTE 2							60	1125								225
STA. 1547+30 TO STA. 1548+90							80	160								160
STA. 1548+90 TO STA. 1555+85							170	695								695
FAI 57 STAGE 4 PROJECT SUBTOTALS								2,370	14,056							10,218
FAI 57 STAGE 4 PROJECT TOTALS								0	0							0

NOTE: 1.) THE LEFT SOLID YELLOW LINE IS 8" WIDE. THEREFORE 2 STRIPS OF 4" TAPE SHALL BE PLACED.

NOTE: 2.) SEE CALCULATIONS AND/OR PLANS FOR CLARIFICATION OF QUANTITIES

PLOT DATE = 1/16/2007
 FILE NAME = c:\pcc\jones\982282\pld13\pld13.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = jbranzjs

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION <h3 style="margin: 0;">SCHEDULE</h3>
NAME	DATE	
SCALE: VERT. HORIZ.		DRAWN BY JCK
DATE		CHECKED BY