CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	378
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SEEDING - FAI 57 STAGE 5

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	REMARKS
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	
RAMP F									
RT STA 4+50 TO STA 15+75	134	1.34	1.34	214	161	161	2.7	2.68	
LT STA 5+50 TO STA 10+75	31	0.31	0.31	50	37	37	0.6	0.62	
LT STA 4+50 TO STA 8+50	8		0.08	10				0.08	
RAMP FF									
RT STA 3+00 TO STA 7+75	54	0.54	0.54	86	65	65	1.1	1.08	
LT STA 4+75 TO STA 7+25	38	0.38	0.38	61	46	46	0.8	0.76	
LT STA 9+50 TO STA 11+00	24	0.24	0.24	38	29	29	0.5	0.48	
FAI 57 STAGE 5 PROJECT TOTALS	289	2.81	2.89	459	338	338	5.7	5.70	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo