

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	382

STA. TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

- FAI 57 & FAU 9529 (OLD IL 13)
- ** (X1-6-2)WB-2, (X1-6)HBK-2

GUARD RAIL - FAI 57 STAGE 5

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED)	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)	GUARDRAIL REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH	
FAI 57 RAMP F													
RT													
STA. 2+39 TO STA. 7+59			500.0	1	1			411.0					CONNECTS TO STRUCTURE #100-0087
RAMP FF													
RT													
STA. 6+46 TO STA. 10+27			312.5				1	1					CONNECTS TO STRUCTURE # 100-0085 - SEE NOTE 1
FAI 57 STAGE 5 PROJECT TOTALS	0.0	0	812.5	1	1	1	1	411.0	0.0	0	0	0	

NOTE: 1.) THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

BARRIER DELINEATION - FAI 57 STAGE 5

LOCATION STA TO STA	GUARDRAIL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKERS DIRECT APPLIED
	EACH	EACH	EACH
FAI 57			
RAMP F			
RT STA 2+39 TO STA 7+59	7		
STA 3+75 TO STA 7+50		5	
RAMP FF			
RT STA 6+46 TO STA 10+27	6		1
FAI 57 STAGE 5 PROJECT TOTALS	13	5	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
DATE

DRAWN BY JCK
CHECKED BY