CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	489
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

CONCRETE PAVEMENT - FAI 57 STAGE 7

LOCATION STA TO STA	PCC PAVEMENT 8" (JOINTED) SQ YD	PCC PAVEMENT 10" (JOINTED) SQ YD	BRIDGE APPROACH PAVEMENT (SPECIAL) SQ YD	PCC DRIVEWAY PAVEMENT 6" SQ YD	PCC DRIVEWAY PAVEMENT 7" SQ YD	PROTECTIVE COAT SQ YD	BRIDGE DECK GROOVING SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE A 6" SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE A 4" SQ YD
FAI 57									
NORTHBOUND									
STA 1515+63 TO STA 1515+93			145			140	137		
STA 1517+26 TO STA 1517+56			144			139	135		
STA 1528+80 TO STA 1529+10			147			142	138		
STA 1530+84 TO STA 1531+14			146			141	138		
SOUTHBOUND									
STA 1515+61 TO STA 1515+91			146			141	137		
STA 1517+24 TO STA 1517+54			148			143	140		
STA 1528+78 TO STA 1529+08			145			140	137		
STA 1530+82 TO STA 1531+12			146			141	138		
FAI 57 STAGE 7 PROJECT TOTALS	**0**	**0**	**1,167**	**0**	**0**	**1,127**	**1,100**	**0**	**0**

SHOULDERS - FAI 57 STAGE 7

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL SQ YD	BITUMINOUS SHOULDERS, SUPERPAVE TON	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 8" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 8 1/2" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 9 1/2" SQ YD	AGGREGATE SHOULDERS, TYPE A 8" SQ YD	AGGREGATE SHOULDERS, TYPE B TON	BITUMINOUS MATERIALS (PRIME COAT) GALLON	SHOULDER RUMBLE STRIP FOOT	REMARKS
FAI 57											
NORTHBOUND											
STA 1513+00 TO STA 1515+62			350.0	117.0					149.0		
STA 1517+55 TO STA 1528+79			1,499.0	500.0					640.0		
STA 1531+13 TO STA 1541+33			1,360.0	454.0					581.0		
FAI 57 STAGE 7 PROJECT TOTALS	**0.0**	**0.0**	**3,209.0**	**1,071.0**	**0.0**	**0.0**	**0.0**	**0.0**	**1,370.0**	**0.0**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 10/25/2006
FILE NAME = c:\projects\x1628602\sht3\sht3sheet32
PLOT SCALE = 60.0000 ' / IN.
USER NAME = kkenzig