

| | | | | |
|---------------------|---------|---------------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| * | ** | WILLIAMSON | 917 | 493 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 7

| LOCATION STA TO STA | EARTH EXCAVATION CU YD | FOR INFORMATION ONLY | | | | | | REMARKS |
|--|------------------------------|-------------------------------------|--|---------------------|---|--------------------------------|-------------------------------|---------|
| | | AVERAGE SHRINKAGE FACTOR % | EARTH EXCAVATION (ADJUSTED) CU YD | EMBANKMENT CU YD | EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD | BORROW SWELL FACTOR % | BORROW EXCAVATION CU YD | |
| | | | | | | | | |
| FAI 57 | | | | | | | | |
| STA 1513+00 TO STA 1542+50 MEDIAN | 27 | 25.6% | 20 | 2,365 | -2,345 | | | |
| STA 1515+92 TO STA 1517+25 BRIDGE CONE | 0 | 17.2% | 0 | 734 | -734 | | | |
| STA 1529+09 TO STA 1530+83 BRIDGE CONE | 1,438 | 36.8% | 908 | 1 | 907 | | | |
| FAI 57 STAGE 7 PROJECT TOTAL | 1,465 | 26.5% | 928 | 3,100 | -2,172 | 25.0% | 2,715 | |

RAISED PAVEMENT MARKERS - FAI 57 STAGE 7

| LOCATION STATION TO STATION | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH | RAISED REFLECTIVE PAVEMENT MARKER | | |
|---|--|--------------------------------------|--------------------------|----------------------------|
| | | ONE-WAY AMBER EACH | TWO-WAY AMBER EACH | ONE-WAY CRYSTAL EACH |
| | | | | |
| FAI 57 | | | | |
| NORTHBOUND | | | | |
| STA. 1505+56 TO STA. 1515+56 | | 26 | | 26 |
| STA. 1517+63 TO STA. 1528+73 | | 28 | | 28 |
| STA. 1531+15 TO STA. 1550+00 | | 48 | | 48 |
| SOUTHBOUND | | | | |
| STA. 1501+60 TO STA. 1515+53 | | 35 | | 35 |
| STA. 1517+61 TO STA. 1528+70 | | 28 | | 28 |
| STA. 1531+19 TO STA. 1550+00 | | 48 | | 48 |
| FAI 57 STAGE 7 PROJECT SUBTOTALS | | | 0 | 213 |
| FAI 57 STAGE 7 PROJECT TOTALS | | 213 | 213 | |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY