CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	495
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

PAVEMENT MARKING REMOVAL - FAI 57 STAGE 7

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL DASH LINE SQ FT	PAVEMENT MARKING REMOVAL SOLID LINE SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
FAI 57				
NORTHBOUND				
STA. 1506+90 TO STA. 1510+48.26 BK	30	239		
STA. 1510+49.47 AH TO STA. 1523+45	107	864		
STA. 1523+45 TO STA. 1524+26	0	228		
STA. 1524+26 TO STA. 1524+85	7	43		
STA. 1524+85 TO STA. 1525+86	10	69		
STA. 1525+86 TO STA. 1538+90	110	869		
STA. 1538+90 TO STA. 1540+00	0	110		
STA. 1540+00 TO STA. 1550+00	83	667		
SOUTHBOUND				
STA. 1501+60 TO STA. 1503+00	0	178		
STA. 1503+00 TO STA. 1503+17	3	28		
STA. 1503+17 TO STA. 1505+90	23	364		
STA. 1505+90 TO STA. 1509+43.5 BK	30	236		
STA. 1509+15.58 AH TO STA. 1510+00	7	56		
STA. 1510+00 TO STA. 1519+25	77	617		
STA. 1519+25 TO STA. 1521+55	20	237		
STA. 1521+55 TO STA. 1522+15	0	85		
STA. 1522+15 TO STA. 1530+27	67	541		
STA. 1530+27 TO STA. 1536+00	47	599		
STA. 1536+00 TO STA. 1537+10	0	110		
STA. 1537+10 TO STA. 1545+05	67	1060		
STA. 1545+05 TO STA. 1547+30	20	450		
STA. 1547+30 TO STA. 1548+90	27	107		
STA. 1548+90 TO STA. 1555+85	57	463		
FAI STAGE 7 PROJECT SUBTOTAL	792	8,220	0	
FAI 57 STAGE 7 PROJECT TOTAL	9,012		0	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/11/2006
FILE NAME = c:\projects\d902802\old13\old13schm32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo