

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	496
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• FAI 57 & FAU 9629 (OLD IL 13)  
•• (X1-6-2)VB-2, (X1-6)HBK-2

**GUARD RAIL - FAI 57 STAGE 7**

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED) EACH	STEEL PLATE BEAM GUARD RAIL, TYPE A FOOT	TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) EACH	GUARDRAIL REMOVAL FOOT	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10 EACH	REMARKS
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	EACH	
<b>FAI 57 NORTHBOUND</b>													
<b>RT (INSIDE SHOULDER)</b>													
STA. 1517+41.9 TO STA. 1517+63								22.0					
STA. 1530+75.7 TO STA. 1531+22								47.0					
<b>SOUTHBOUND</b>													
<b>LT (INSIDE SHOULDER)</b>													
STA. 1515+53 TO STA. 1515+76.8								24.0					
STA. 1528+70 TO STA. 1529+09								40.0					
<b>FAI 57 STAGE 7 PROJECT TOTALS</b>	0.0	0	0.0	0	0	0	0	133.0	0.0	0	0	0	

**CONCRETE BARRIER - FAI 57 STAGE 7**

LOCATION STATION TO STATION	CONCRETE BARRIER, DOUBLE FACE 42 INCH HEIGHT	TEMPORARY CONCRETE BARRIER FOOT	RELOCATE TEMPORARY CONCRETE BARRIER FOOT	PROTECTIVE COAT SQ YD	REMARKS
	FOOT	FOOT	FOOT	SQ YD	
<b>FAI 57 NORTHBOUND</b>					
STA 1513+00 TO STA 1544+64				3,175	
STA 1513+00 TO STA 1515+62	262			291	
STA 1515+62 TO STA 1515+92				34	MEDIAN BRIDGE APPROACH BARRIER
STA 1517+25 TO STA 1517+55				34	MEDIAN BRIDGE APPROACH BARRIER
STA 1517+55 TO STA 1528+79	1,124			1,249	
STA 1528+79 TO STA 1529+09				34	MEDIAN BRIDGE APPROACH BARRIER
STA 1530+83 TO STA 1531+13				34	MEDIAN BRIDGE APPROACH BARRIER
STA 1531+13 TO STA 1541+33	1,020			1,134	
<b>SOUTHBOUND</b>					
STA 1507+73 TO STA 1542+33				3,500	
<b>FAI 57 STAGE 7 PROJECT TOTALS</b>	2,406	0	6,675	2,810	

PLT DATE = 12/5/08B5  
FILE NAME = c:\projects\p98950\d92282\0131\0131tab4.c32  
PLOT SCALE = 50.0000' / 1" IN.  
USER NAME = hnanzjjs

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SCHEDULE</b>

SCALE: VERT. \_\_\_\_\_  
       HORIZ. \_\_\_\_\_  
DATE: \_\_\_\_\_

DRAWN BY JCK  
CHECKED BY \_\_\_\_\_