

F.A. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	540
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- \*\* 0X1-6-2(WB-2, 0X1-6(HBK-2

### EARTHWORK - FAI 57 STAGE 7C

LOCATION STA TO STA	EARTH EXCAVATION CU YD	FOR INFORMATION ONLY					BORROW EXCAVATION CU YD	REMARKS
		AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD	BORROW SWELL FACTOR %		
<b>FAI 57</b>								
STA 1506+50 TO STA 1513+00 MEDIAN	23	34.8%	15	193	-178			
STA 1541+33 TO STA 1542+50 MEDIAN	4	35.9%	3	27	-24			
<b>FAI 57 STAGE 7C PROJECT TOTAL</b>	<b>27</b>	<b>35.4%</b>	<b>18</b>	<b>220</b>	<b>-202</b>	<b>25.0%</b>	<b>253</b>	

PLOT DATE = 1/16/2007  
 PLOT TIME = 10:00:00 AM  
 PLOT SCALE = 50.0000 / IN  
 USER NAME = krenstje

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<b>SCHEDULE</b>	
		SCALE: VERT. DATE:       HORIZ.	
		DRAWN BY JCK CHECKED BY	