

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	592
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHOULDERS - FAI 57 STAGE 8

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE	AGGREGATE SHOULDERS, TYPE A	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	TON	6 1/2" SQ YD	8" SQ YD	8 1/2" SQ YD	9 1/2" SQ YD	8" SQ YD	TON	GALLON	FOOT	
FAI 57											
NORTHBOUND											
RT (INSIDE SHOULDER)											
STA 1505+94 TO STA 1506+90		6								96	
STA 1506+90 TO STA 1510+48.2 BK		22							24	359	
STA 1510+49.4 AH TO STA 1515+62		31							34	513	
STA 1517+55 TO STA 1528+79		69							73	1,124	
STA 1531+13 TO STA 1543+08		73							78	1,195	
STA 1543+08 TO STA 1551+75										867	
LT (OUTSIDE SHOULDER)											
STA 1505+94 TO STA 1506+90		7							7	96	
STA 1506+90 TO STA 1513+25		58							61	635	
STA 1513+25 TO STA 1515+65		22							23	240	
STA 1517+58 TO STA 1519+05										147	
STA 1517+58 TO STA 1519+58									13		
STA 1519+05 TO STA 1519+63									3		
STA 1519+05 TO STA 1526+50									98		
STA 1519+56 TO STA 1523+45	87								105	745	
STA 1525+09 TO STA 1525+86	17										
STA 1525+92 TO STA 1528+82									18		
STA 1526+50 TO STA 1528+82										232	
STA 1531+16 TO STA 1534+86									26	370	
STA 1534+86 TO STA 1537+02									26	216	
STA 1537+02 TO STA 1543+08									85	606	
STA 1537+02 TO STA 1546+65	214										
STA 1543+08 TO STA 1550+00										692	
SOUTHBOUND											
RT (OUTSIDE SHOULDER)											
STA 1506+41 TO STA 1509+43.5 BK		34							37	303	
STA 1509+15.5 AH TO STA 1513+25		46							49	410	
STA 1513+25 TO STA 1515+60		28							30	235	
STA 1517+53 TO STA 1519+39									16	186	
STA 1517+53 TO STA 1519+83									15		
STA 1519+39 TO STA 1519+85									2		
STA 1519+39 TO STA 1527+11									101		
STA 1522+50 TO STA 1526+45	88								108	772	
STA 1526+81 TO STA 1528+77									13		
STA 1527+11 TO STA 1528+77										166	
STA 1531+11 TO STA 1534+47									24	336	
STA 1531+12 TO STA 1542+33	249										
STA 1534+47 TO STA 1543+08									69	861	
STA 1542+33 TO STA 1544+96	59										
STA 1543+08 TO STA 1556+00										1,292	
LT (INSIDE SHOULDER)											
STA 1507+18 TO STA 1509+43.5 BK		14							15	226	
STA 1509+15.5 AH TO STA 1515+62		39							42	647	
STA 1517+55 TO STA 1528+79		69							73	1,124	
STA 1531+13 TO STA 1543+08		73							78	1,195	
STA 1543+08 TO STA 1556+85										1,377	
FAI 57 STAGE 8 PROJECT TOTALS											
	714.0	1,074.0	0.0	0.0	0.0	0.0	0.0	0.0	1,132.0	17,263.0	

PLOT DATE = 12/11/2006
 PLOT TIME = 10:42:02
 PLOT SCALE = 50,0000 / IN.
 USER NAME = NRENZUS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY JCK		CHECKED BY _____