CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	597
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EROSION CONTROL - FAI 57 STAGE 8

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL)	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION	END SECTIONS 8"	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	CU YD	TON	EACH	EACH	EACH	
FAI 57										
NORTHBOUND										
LT STA 1519+18 TO STA 1521+00			172.0							
LT STA 1519+50 TO STA 1525+80		792.0								
LT STA 1520+15							1.0			
LT STA 1520+47							1.0			
LT STA 1520+73							1.0			
LT STA 1521+00							1.0			
LT STA 1524+00 TO STA 1526+70			338.0							
LT STA 1524+00							1.0			
LT STA 1524+20							1.0			
LT STA 1524+53							1.0			
LT STA 1524+78							1.0			
LT STA 1525+15							1.0			
LT STA 1525+46							1.0			
LT STA 1525+82							1.0			
LT STA 1526+15							1.0			
LT STA 1537+00 TO STA 1546+66		1,240.0								
SOUTHBOUND										
RT STA 1519+39 TO STA 1523+00			336.0							
RT STA 1520+00 TO STA 1526+62		795.0								
RT STA 1520+65							1.0			
RT STA 1521+15							1.0			
RT STA 1521+65							1.0			
RT STA 1522+00							1.0			
RT STA 1523+00							1.0			
RT STA 1525+00 TO STA 1527+00			186.0							
RT STA 1525+00							1.0			
RT STA 1525+32							1.0			
RT STA 1525+61							1.0			
RT STA 1525+87							1.0			
RT STA 1526+15							1.0			
RT STA 1531+27 TO STA 1545+00		2,688.0								
FAI 57 STAGE 8 PROJECT TOTAL	**0.0**	**5,515.0**	**1,032.0**	**0.0**	**0.0**	**0.0**	**22.0**	**0.0**	**0.0**	

SEEDING - FAI 57 STAGE 8

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
NORTHBOUND								
LT STA 1519+05 TO STA 1526+50	69	0.69	0.69	110	83	83	1.4	1.38
LT STA 1537+90 TO STA 1546+66	62	0.62	0.62	99	74	74	1.2	1.24
SOUTHBOUND								
RT STA 1519+39 TO STA 1526+50	63	0.63	0.63	101	76	76	1.3	1.26
RT STA 1530+72 TO STA 1544+50 NOTE 1	86	2.00	0.86	183	240	240	4.0	2.86
FAI 57 STAGE 8 PROJECT TOTALS	280	3.94	2.80	493	473	473	7.9	6.74

NOTE 1: TEMPORARY SEEDING PLACED IN STAGE 3 AND 4

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\projects\s9902802\sld13\sch_ms32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje