

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	599A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

PAVEMENT MARKING REMOVAL - FAI 57 STAGE 8

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL		WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
	DASH LINE	SOLID LINE		
	SQ FT	SQ FT		
FAI 57				
NORTHBOUND				
STA 1506+90 TO STA 1510+48.26 BK	5	21	28.0	
STA 1510+49.47 AH TO STA 1510+93	6	44		
STA 1510+93 TO STA 1513+25	30	239	6.7	
STA 1513+25 TO STA 1514+10	4	29		
STA 1514+10 TO STA 1516+60	19	155	66.7	
STA 1516+60 TO STA 1517+63	7	57		
STA 1517+63 TO STA 1519+07	26	102		
STA 1519+07 TO STA 1525+87	0	0	44.0	
STA 1525+87 TO STA 1528+25	0	0	16.0	
STA 1528+25 TO STA 1531+88	0	0	41.3	
STA 1531+88 TO STA 1534+86	12	144		
STA 1534+86 TO STA 1542+00	57	453	49.3	
STA 1542+00 TO STA 1543+00	7	55		
STA 1543+00 TO STA 1550+00	13	207		
STA 1550+00 TO STA 1551+75	5	37		
SOUTHBOUND				
STA 1500+00 TO STA 1502+12	8	67		
STA 1502+12 TO STA 1503+12	58	467		
STA 1503+12 TO STA 1508+10	0	0		
STA 1508+10 TO STA 1509+43.5 BK	0	0	29.3	
STA 1509+15.58 AH TO STA 1513+00	0	0	16.0	
STA 1513+00 TO STA 1515+53	0	0	45.3	
STA 1515+53 TO STA 1519+39	0	67	37.3	
STA 1519+39 TO STA 1542+33	0	34	46.7	
STA 1542+33 TO STA 1547+25	18	146	149.3	
STA 1547+25 TO STA 1556+00	15	117		
STA 1556+00 TO STA 1556+85	23	89		
FAI STAGE 8 PROJECT SUBTOTAL		313	2,530	576
FAI 57 STAGE 8 PROJECT TOTAL		2,843		576

PLOT DATE = 2/13/2007
 FILE NAME = c:\projects\982282\ad13\ad13sch.m32
 PLOT SCALE = 50.0000 / IN.
 USER NAME = krenzjp

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SCHEDULE SCALE: VERT. HORIZ. DATE	
		CHECKED BY	