

SUMMARY OF QUANTITIES

PAINT PAVEMENT MARKING SCHEDULE

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	WHITE COUNTY			
				ROADWAY RURAL 80% FED/20% ST	SN 097-0029 RURAL 80% FED/20% ST	SN 097-0036 RURAL 80% FED/20% ST	SN 097-0064 RURAL 80% FED/20% ST
	CONSTRUCTION TYPE CODE			1000	5FTY-2A	5FTY-2A	5FTY-2A
35102000	AGGREGATE BASE COURSE TYPE B, 8"	SO YD	400	400			
40600100	BITUMINOUS MATERIALS PRIME COAT	GALLON	21,872	21,838	19		15
40600300	AGGREGATE PRIME COAT	TON	365	363	1		1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33			
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	5253	5,244	5		4
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	178	178			
40600990	TEMPORARY RAMP	SO YD	251	251			
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	10,803	10,786	9		8
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	98	98			
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	103		103		80
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	93,018	93,018			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	28,310	28,310			
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SO YD	328	328			
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	2,223	2,223			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	85,203	85,203			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	873	873			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	104	104			
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	14	14			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	19	4	3	8	4
63200310	GUARDRAIL REMOVAL	FOOT	526	126	75	225	100
67100100	MOBILIZATION	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,619	11,619			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	125,732	125,732			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	45,784	45,784			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	125,732	125,732			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	533	533			
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	4	4			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	19	4	3	8	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	533	533			
X0322729	MATERIAL TRANSFER DEVICE	TON	15,301	15,275	14		12

LOCATION STATION TO STATION				PAINT PAVEMENT MARKING			
				LINE - 4" YELLOW		LINE - 4" WHITE	
LEFT SOLID	CENTER DASHED	RIGHT SOLID	SOLID	FEET	FEET **		
STA. 145+93	TO STA. 154+48.58 BK =			213.9	1,711.2		
STA. 6+40.19 AH	TO STA. 10+70			107.5	859.6		
STA. 10+70	TO STA. 19+25			213.8	1,710.0		
STA. 19+25	TO STA. 53+45	3,420.0	855.0	3,420.0	6,840.0		
STA. 53+45	TO STA. 63+70	1,025.0	256.3		2,050.0		
STA. 63+70	TO STA. 67+60		97.5		780.0		
STA. 67+60	TO STA. 80+10		312.5	1,250.0	2,500.0		
STA. 80+10	TO STA. 90+65	1,055.0		1,055.0	2,110.0		
STA. 90+65	TO STA. 100+30		241.3		1,930.0		
STA. 100+30	TO STA. 106+50		155.0		1,240.0		
STA. 106+50	TO STA. 116+35		246.3	985.0	1,970.0		
STA. 116+35	TO STA. 130+50	1,415.0		1,415.0	2,830.0		
STA. 130+50	TO STA. 141+20	1,070.0	267.5		2,140.0		
STA. 141+20	TO STA. 153+97		319.3		2,554.0		
STA. 153+97	TO STA. 164+20		255.8	1,023.0	2,046.0		
STA. 164+20	TO STA. 165+05		85.0	85.0	170.0		
STA. 165+05	TO STA. 176+00	1,095.0	273.8		2,190.0		
STA. 176+00	TO STA. 177+67.5		41.9		335.0		
STA. 177+67.5	TO STA. 178+77.5			OMISSION			
STA. 178+77.5	TO STA. 239+64		1,521.6		12,173.0		
STA. 239+64	TO STA. 240+06			OMISSION			
STA. 240+06	TO STA. 244+30		106.0		848.0		
STA. 244+30	TO STA. 251+90		190.0	760.0	1,520.0		
STA. 251+90	TO STA. 252+40	50.0		50.0	100.0		
STA. 252+40	TO STA. 262+05	965.0	241.3		1,930.0		
STA. 262+05	TO STA. 269+70		191.3		1,530.0		
STA. 269+70	TO STA. 276+60		172.5	690.0	1,380.0		
STA. 276+60	TO STA. 279+60		75.0		600.0		
STA. 279+60	TO STA. 287+10	750.0	187.5		1,500.0		
STA. 287+10	TO STA. 299+50		310.0		2,480.0		
STA. 299+50	TO STA. 309+75		256.3	1,025.0	2,050.0		
STA. 309+75	TO STA. 331+04	2,129.0		2,129.0	4,258.0		
STA. 331+04	TO STA. 341+35	1,031.0	257.8		2,062.0		
STA. 341+35	TO STA. 398+96		1,440.3		11,522.0		
STA. 398+96	TO STA. 404+61		141.3	565.0	1,130.0		
STA. 404+61	TO STA. 408+84		105.8		846.0		
STA. 408+84	TO STA. 414+13	529.0	132.3		1,058.0		
STA. 414+13	TO STA. 423+67		238.5		1,908.0		
STA. 423+67	TO STA. 425+38		42.8	171.0	342.0		
SUBTOTAL				15,584.0	9,466.9	15,478.0	85,202.8
TOTAL				125,732			

** Accounts for double edge line striping

* SPECIALTY ITEMS

PLOT DATE = 1/17/2007
 FILE NAME = c:\pvc\mca\pvc\2285\982285.dwg
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = colson