

INDEX TO SHEETS	
SHEET NUMBER	SHEET TITLE
01	COVER SHEET
02	INDEX TO SHEETS - SUMMARY OF QUANTITIES
03	SITE PLAN - HORIZONTAL AND VERTICAL CONTROL PLAN
04	SEQUENCE OF CONSTRUCTION - GENERAL NOTES - CRITICAL POINTS
05	SEQUENCE OF CONSTRUCTION - PHASE 1
06	SEQUENCE OF CONSTRUCTION - PHASE 2
07	SEQUENCE OF CONSTRUCTION - DETAILS
08	EXISTING CONDITIONS & DEMOLITION - STA. 1+00 TO STA. 12+00
09	EXISTING CONDITIONS & DEMOLITION - STA. 12+00 TO STA. 26+00
10	EXISTING CONDITIONS & DEMOLITION - STA. 26+00 TO STA. 40+00
11	PAVEMENT MARKINGS - RUNWAY 9-27
12	PAVEMENT MARKINGS - AIRFIELD LETTERS AND SYMBOLS
13	AIRFIELD LIGHTING PLAN - STA. 1+00 TO STA. 12+00
14	AIRFIELD LIGHTING PLAN - STA. 12+00 TO STA. 26+00
15	AIRFIELD LIGHTING PLAN - STA. 26+00 TO STA. 40+00
16	AIRFIELD LIGHTING PLAN - ELECTRICAL VAULT
17	AIRFIELD SIGNING PLAN - RUNWAY 9-27
18	ELECTRICAL DETAILS - AIRFIELD LIGHTING - GENERAL DETAILS
19	ELECTRICAL DETAILS - AIRFIELD LIGHTING - EDGE LIGHTS
20	ELECTRICAL DETAILS - AIRFIELD LIGHTING - THRESHOLD LIGHTS
21	ELECTRICAL DETAILS - AIRFIELD LIGHTING - WIND CONE

SUMMARY OF QUANTITIES				
ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	RECORD
BASE BID				
AR107408	L - 806 WIND CONE - 8' LIGHTED	EACH	1	
AR107900	REMOVE WIND CONE	EACH	1	
AR108108	1/C #8 5 KV UG CABLE	L.F.	2,550	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	17,500	
AR109210	VAULT MODIFICATIONS	L.S.	1	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	9	
AR125410	MITL - STAKE MOUNTED	EACH	107	
AR125415	MITL - BASE MOUNTED	EACH	11	
AR125505	MIRL, STAKE MOUNTED	EACH	21	
AR125510	MIRL, BASE MOUNTED	EACH	12	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	8	
AR125545	MI THRESHOLD LIGHT BASE MTD	EACH	8	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	122	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	28	
AR125986	REFURBISH REILS	PAIR	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	42	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	8,400	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	1,195	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	3,600	
AR800140	2 1/C # 6 XLP-USE, 1/C # 10 GND - 1" UD	L.F.	1,000	
AR800187	THRESHOLD LIGHT BAR	EACH	2	
AR800894	RETROFIT EXIST MITL OR TXY SIGN	EACH	39	
ADD. ALT. NO.1				
AS125442	TAXIWAY GUIDANCE SIGN, 2 CHARACTE	EACH	1	
AS125443	TAXIWAY GUIDANCE SIGN, 3 CHARACTE	EACH	1	
AS125445	TAXIWAY GUIDANCE SIGN, 5 CHARACTE	EACH	2	
AS125904	REMOVE TAXIWAY GUIDANCE SIGN	EACH	4	
ADD. ALT. NO.2				
AT125442	TAXIWAY GUIDANCE SIGN, 2 CHARACTE	EACH	10	

IL. CONTRACT: LA036
 IL. LETTING ITEM: 2A
 IL. PROJECT: IGQ-3565
 A.I.P. PROJECT: 3-17-0121-825

SURVEY BOOK # BOOK #

REVISIONS		
NUMBER	BY	DATE

0 1 2
 THIS BAR IS EQUAL TO 2"
 AT FULL SCALE (34X22).

VILLAGE OF LANSING
 LANSING MUNICIPAL AIRPORT
 LANSING, ILLINOIS

REHABILITATE AIRFIELD LIGHTING SYSTEM
 INDEX TO SHEETS
 SUMMARY OF QUANTITIES

© Copyright GMT, Inc.

GMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 83-006615

Lansing Municipal
airport

DESIGN BY: JWD
 DRAWN BY: JWD
 CHECKED BY: DKP
 APPROVED BY: ----
 DATE: 02 MARCH 2007
 JOB No: 06297-02

G-02