SIDEWALK REMOVAL — TOTAL 19312 SQ FT

LOCATION	FROM STA.	TO STA.	OFFSET RT. / LT.	SUBTOTALS
McLEAN BLVD. & FLEETWOOD DR. S.E. QUADRANT				257
McLEAN BLVD.	65+32.87	67+73.05	RT.	1447
McLEAN BLVD.	68+04.14	69+14.05	RT.	541
McLEAN BLVD.	64+86.29	67+73.62	LT.	1399
McLEAN BLVD.	68+07.94	71+86.50	LT.	1495
McLEAN BLVD.	72+35.78	76+20.46	RT.	1778
McLEAN BLVD.	72+40.87	76+08.00	LT.	1774
McLEAN BLVD.	76+50.43	78+58.21	LT.	1015
McLEAN BLVD.	76+73.84	76+87.76	RT.	95
McLEAN BLVD.	77+13.04	77+72.66	RT.	272
McLEAN BLVD.	77+94.56	78+19.76	RT.	142
McLEAN BLVD.	78+35.98	78+76.80	RT.	150
McLEAN BLVD.	79+11.62	79+90.28	RT.	386
McLEAN BLVD.	79+12.18	79+38.03	LT.	328
McLEAN BLVD.	79+56.12	80+04.24	LT.	178
McLEAN BLVD.	80+11.05	80+73.31	RT.	299
McLEAN BLVD.	80+21.57	80+68.07	LT.	170
McLEAN BLVD.	80+90.18	81+20.38	LT.	125
McLEAN BLVD.	81+04.39	81+35.20	RT.	143
McLEAN BLVD.	81+60.56	81+98.65	RT.	306
McLEAN BLVD.	81+61.47	82+59.70	LT.	591
McLEAN BLVD. & LILLIAN ST. S. E. QUADRANT				212
McLEAN BLVD. & LILLIAN ST. N. W. QUADRANT				99
McLEAN BLVD.	83+20.45	85+29.58	RT.	975
McLEAN BLVD.	85+63.61	85+87.69	RT.	90
McLEAN BLVD.	86+30.19	86+83.08	RT.	527
McLEAN BLVD.	86+89.90	88+27.26	LT.	538
McLEAN BLVD.	87+18.66	87+79.06	RT.	227
McLEAN BLVD.	88+04.02	88+46.81	RT.	166
McLEAN BLVD.	88+69.57	89+24.17	RT.	233
McLEAN BLVD.	88+60.28	88+86.75	LT.	97
McLEAN BLVD.	88+97.00	89+00.00	LT.	9
LILLIAN ST	198+89.40	199+12.00	RT.	112
LILLIAN ST	201+18.48	202+48.38	LT.	506
LILLIAN ST	202+62.62	203+46.87	LT.	427
LILLIAN ST	200+97.93	201+30.40	RT.	115
LILLIAN ST			RT.	174
LILLIAN ST	202+17.40	203+48.35	RT.	592
BUILDING # 6	along US 20 RT	115+53.83	RT.	169
ELM GROVE DRIVE	along US 20 LT	113+41.51	RT.	318
ELM GROVE DRIVE	along US 20 LT	113+72.79	RT.	328
BLDG RMVL # 1	WEST OF BLDG			100
BLDG RMVL # 2	WEST OF BLDG			406

CONCRETE BARRIER REMOVAL — TOTAL 3541 FOOT

LOCATION	FROM STA.	TO STA.	SUBTOTALS
US 20	99+15.95	113+57.87	1442
US 20	119+24.70	140+24.00	2099

PAVED SHOULDER REMOVAL — TOTAL 15701 SQ YD

LOCATION		FROM STA.	TO STA.	SUBTOTALS
US 20 W.B. RT. SHLD.		70+00.00	96+59.85	2,339
US 20 W.B. RT. SHLD. & W.B. ON RAMP	LT. SHLD.	86+72.88	97+52.11	1,252
US 20 W.B. LT		70+00.00	78+50.00	532
US 20 W.B. LT		84+50.00	97+57.00	906
WELD RD. W.B. CROSS OVER, SHOULDERS.	RT. SHLD.			118
WELD RD. W.B. CROSS OVER, SHOULDERS.	LT. SHLD.			81
US 20 W.B. LT. SHLD.		99+04.90	113+57.83	752
US 20 W.B. RT. SHLD. & W.B. OFF RAMP	LT. SHLD.	99+00.00	109+49.71	1,464
US 20 E.B. LT. SHLD.		99+08.22	113+57.88	751
E.B. ON RAMP SHOULDERS	RT. SHLD.			196
E.B. ON RAMP SHOULDERS	LT. SHLD.			177
US20 W.B. RT. SHLD. & W.B. OFF RAMP	RT. SHLD.	99+07.00	140+24.00	3,639
US20 E.B. LT. SHOULDER		119+25.00	140+24.00	727
US20 W.B. LT. SHOULDER		119+25.00	140+24.00	590
WELD RD EB RT (PREVIOUS WELD RD CONNECTION)				9
US 20 MEDIAN **		140+24.00	153+41.34	1192
US 20 MEDIAN ***		99+15.93	113+57.88	398
		119+25.00	140+24.00	579

MEDIAN REMOVAL — TOTAL 122 SQ FT

	SUBTOTALS
WELD RD. at McLEAN BLVD. - CENTER MEDIAN	122

AGGREGATE SHOULDERS, TYPE B 4" — TOTAL 7443 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
US20 W.B. LT.	56+60.50	86+00.00	1,306
RAMP A W.B. RT.	11+74.33	33+60.22	972
RAMP D WB RT.	02+96.95	03+90.09	41
RAMP D WB RT.	07+92.10	23+95.03	712
US20 W.B. RT.	101+66.18	107+38.58	254
US20 W.B. RT.	89+94.24	94+98.86	224
US20 W.B. RT.	133+00.00	141+68.15	386
US20 E.B. LT.	56+50.00	86+00.00	1,311
US20 E.B. RT.	68+54.05	79+97.20	508
RAMP C E.B. RT.	09+39.38	10+79.05	62
RAMP B E.B.RT.	04+56.53	05+99.65	64
RAMP B E.B.RT.	14+20.74	24+25.25	446
US20 E.B. RT.	90+67.80	94+93.72	189
US20 E.B. RT.	101+65.92	106+67.24	223
US20 E.B. RT.	122+50.00	139+22.24	743

AGGREGATE SHOULDERS, TYPE B 10" — TOTAL 1838 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
US 20 E.B.RT	64+37.00	68+54.05	92.68
RAMP C LT	8+21.77	16+26.07	178.73
RAMP C RT	10+79.05	17+97.31	159.61
US 20 E.B.RT	88+19.39	90+67.80	55.20
US 20 E.B.RT	106+67.24	108+35.37	37.36
RAMP B RT	1+14.02	4+56.56	76.12
RAMP B LT	3+44.62	10+03.66	146.45
US 20 E.B. RT	139+22.24	156+01.87	373.25
US 20 W.B. RT	107+38.58	109+06.08	37.22
RAMP A LT	29+13.01	37+83.07	193.35
RAMP A RT	33+60.22	39+42.86	129.48
RAMP D RT	1+57.40	2+96.92	31.00
RAMP D LT	2+69.75	10+73.80	178.68
US 20 W.B. RT	87+15.05	89+94.64	62.13
US 20 W.B. RT	70+00.00	73+92.42	87.20

AGGREGATE WEDGE SHOULDER, TYPE B — TOTAL 73 TON

LOCATION	STA.	STA.	LENGTH FT	VOLUME CU. YDS.	SUBTOTALS
US 20 W.B. LT	55+00.00	56+60.50	160.50	1.85	3.80
US 20 W.B. RT	55+00.00	70+00.00	1,500.00	17.33	35.53
US 20 W.B. RT	141+68.15	156+01.87	1,433.72	16.57	33.96

PORTLAND CEMENT CONCRETE SHOULDERS 10" — TOTAL 10470 SQ YD

LOCATION	STA.	STA.	SUBTOTALS
RAMP A (RT)	39+43.75	27+05.09	1,624
RAMP A (LT)	37+84.15	29+13.01	950
RAMP B (RT)	1+13.34	14+72.13	1,769
RAMP B (LT)	3+44.62	10+03.66	697
RAMP C (RT)	4+61.69	17+98.81	1,780
RAMP C (LT)	4+61.69	16+26.07	863
RAMP D (RT)	16+41.14	1+57.51	1,933
RAMP D (LT)	10+73.80	2+69.31	854

PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4" — TOTAL 29711 SQ YD

LOCATION US 20	FROM STA.	TO STA.	SUBTOTALS
W.B. OUTSIDE SHOULDER (RT.)			
US 20	140+24.00	27+05.09	4,108
US 20	111+15.77	101+66.47	1,199
US 20	94+98.93	81+46.72	1,637
US 20	81+46.72	70+00.00	1,531
W.B. INSIDE SHOULDER (LT.)			
US 20	70+00.00	93+98.85	2,133
US 20	93+98.85	94+98.89	129
US 20	101+66.35	102+65.32	128
US 20	102+65.32	140+24.00	3,588
E.B. OUTSIDE SHOULDER (RT.)			
US 20	70+00.00	84+59.50	2,057
US 20	84+59.50	94+99.12	1,398
US 20	101+65.92	112+99.71	1,472
US 20	112+99.71	122+50.00	1,339
US 20	112+50.00	140+24.00	2,365
E.B. INSIDE SHOULDER (LT.)			
US 20	70+00.00	93+98.85	2,764
US 20	93+98.85	94+98.89	129
US 20	101+66.35	102+65.32	129
US 20	102+65.32	140+24.00	3,605

CONCRETE CURB, TYPE B — TOTAL 749 FOOT

LOCATION	FROM STA.	TO STA.	LENGTH FT	SUBTOTALS
US 20 UNDER STRUCTURE OVER McLEAN BLVD.				
UNDER US 20 E.B, RT	95+67.54	97+34.49	166.95	167
UNDER US 20 E.B, LT	95+65.95	97+16.95	151.00	151
UNDER US 20 W.B, RT	99+30.43	100+95.32	164.89	165
UNDER US 20 W.B, LT	99+39.78	100+95.71	155.93	156
US 20 E.B.	94+93.72	94+99.18	5.50	6
LILLIAN	197+72.90	197+77.70	7.63	8
LILLIAN	201+31.68		39.79	40
McLEAN BLVD	77+74.04		2.30	2
McLEAN BLVD	77+94.99		1.00	1
CORNER ISLAND - S.W. QUADRANT AT McLEAN BLVD & FLEETWOOD DR.				
			35.00	35
McLEAN BLVD	87+79.00		6.50	7
McLEAN BLVD	88+03.00		9.50	10
McLEAN BLVD	68+08.00		3.40	3

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06 — TOTAL 418 FOOT

LOCATION	FROM STA.	TO STA.	SUBTOTALS
McLEAN BLVD. N.B. LT.	68+07.34	70+44.16	239
McLEAN BLVD. S.B. LT.	67+70.61	69+23.34	154
CORNER ISLAND IN S.W. QUADRANT OF McLEAN BLVD. AND FLEETWOOD AVE.			25

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 — TOTAL 3067 FOOT

LOCATION	FROM STA.	TO STA.	SUBTOTALS
FLEETWOOD DR. E.B. RT	310+83.12	312+50.40	188
FLEETWOOD DR. MEDIAN	310+88.40	311+77.20	187
McLEAN BLVD. N.B. RT.	58+00.00	62+90.00	487
McLEAN BLVD. N.B. RT.	64+10.00	69+10.00	471
McLEAN BLVD. N.B. RT.	71+20.00	71+71.00	70
McLEAN BLVD. N.B. RT.	75+06.00	75+13.00	10
McLEAN BLVD. N.B. RT.	76+59.82	88+27.00	1,142
LILLIAN (N.EDGE)	200+92.00	203+40.30	249
LILLIAN (S.EDGE)	200+96.10	202+98.40	203
ELM GROVE DR (US20 STATIONING)	113+21.50	113+71.64	61