

EARTHWORK SCHEDULE

STA FROM	TO STA	EARTH EXCAVATION		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS		PGES PLACEMENT		EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)		EMBANKMENT		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
		STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
TEMPORARY RAMP A													
403+00.00	403+50.00	3.7	0.0	0.0	0.0	0.0	0.0	3.2	0.0	0.0	0.0	3.2	0.0
403+50.00	404+00.00	4.4	0.0	0.0	0.0	0.0	0.0	3.7	0.0	0.9	0.0	2.8	0.0
404+00.00	404+50.00	2.9	0.0	5.6	0.0	0.0	0.0	2.5	0.0	11.0	0.0	-8.5	0.0
404+50.00	405+00.00	2.7	0.0	26.5	0.0	0.0	0.0	2.3	0.0	48.5	0.0	-46.2	0.0
405+00.00	405+50.00	0.5	0.0	47.9	0.0	0.0	0.0	0.4	0.0	125.8	0.0	-125.4	0.0
405+50.00	406+00.00	0.0	0.0	56.7	0.0	0.0	0.0	0.0	0.0	237.6	0.0	-237.6	0.0
406+00.00	406+50.00	0.0	0.0	62.4	0.0	0.0	0.0	0.0	0.0	370.1	0.0	-370.1	0.0
406+50.00	407+00.00	0.0	0.0	67.7	0.0	0.0	0.0	0.0	0.0	432.9	0.0	-432.9	0.0
407+00.00	407+50.00	0.0	0.0	72.4	0.0	0.0	0.0	0.0	0.0	410.2	0.0	-410.2	0.0
407+50.00	408+00.00	0.0	0.0	74.9	0.0	0.0	0.0	0.0	0.0	315.8	0.0	-315.8	0.0
408+00.00	408+50.00	0.0	0.0	66.2	0.0	0.0	0.0	0.0	0.0	183.4	0.0	-183.4	0.0
408+50.00	409+00.00	0.0	0.0	56.4	0.0	0.0	0.0	0.0	0.0	96.1	0.0	-96.1	0.0
409+00.00	409+50.00	2.1	0.0	55.8	0.0	0.0	0.0	1.8	0.0	41.8	0.0	-40.1	0.0
409+50.00	410+00.00	4.6	0.0	56.0	0.0	0.0	0.0	3.9	0.0	18.4	0.0	-14.5	0.0
410+00.00	410+50.00	3.1	0.0	55.7	0.0	0.0	0.0	2.6	0.0	23.8	0.0	-21.2	0.0
410+50.00	411+00.00	0.6	0.0	55.4	0.0	0.0	0.0	0.5	0.0	35.1	0.0	-34.6	0.0
411+00.00	411+50.00	0.1	0.0	55.3	0.0	0.0	0.0	0.1	0.0	49.6	0.0	-49.6	0.0
411+50.00	412+00.00	0.0	0.0	55.4	0.0	0.0	0.0	0.0	0.0	70.0	0.0	-70.0	0.0
412+00.00	412+50.00	0.0	0.0	54.1	0.0	0.0	0.0	0.0	0.0	78.6	0.0	-78.6	0.0
412+50.00	412+92.53	0.0	0.0	22.5	0.0	0.0	0.0	0.0	0.0	33.1	0.0	-33.1	0.0
412+92.53	END												
	SUB-TOTAL	24.7	0.0	946.8	0.0	0.0	0.0	21.0	0.0	2582.7	0.0	-2561.7	0.0
TEMPORARY RAMP B													
500+00.00	500+50.00	4.8	0.0	15.4	0.0	0.0	0.0	4.1	0.0	20.8	0.0	-16.7	0.0
500+50.00	501+00.00	5.9	0.0	47.4	0.0	0.0	0.0	5.1	0.0	150.5	0.0	-145.4	0.0
501+00.00	501+50.00	1.1	0.0	74.3	0.0	0.0	0.0	0.9	0.0	371.9	0.0	-371.0	0.0
501+50.00	502+00.00	0.0	0.0	92.7	0.0	0.0	0.0	0.0	0.0	583.3	0.0	-583.3	0.0
502+00.00	502+50.00	0.0	0.0	98.9	0.0	0.0	0.0	0.0	0.0	758.9	0.0	-758.9	0.0
502+50.00	503+00.00	0.0	0.0	84.8	0.0	0.0	0.0	0.0	0.0	849.4	0.0	-849.4	0.0
503+00.00	503+50.00	0.0	0.0	60.5	0.0	0.0	0.0	0.0	0.0	800.7	0.0	-800.7	0.0
503+50.00	504+00.00	0.0	0.0	36.4	0.0	0.0	0.0	0.0	0.0	655.3	0.0	-655.3	0.0
504+00.00	504+50.00	0.0	0.0	12.2	0.0	0.0	0.0	0.0	0.0	521.9	0.0	-521.9	0.0
504+50.00	505+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	382.8	0.0	-382.8	0.0
505+00.00	505+55.38	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	162.9	0.0	-162.9	0.0
505+55.38	END												
	SUB-TOTAL	11.9	0.0	522.5	0.0	0.0	0.0	10.1	0.0	5258.5	0.0	-5248.3	0.0

STA FROM	TO STA	EARTH EXCAVATION		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS		PGES PLACEMENT		EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)		EMBANKMENT		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
		STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA	STAGE IA	STAGE IIA
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
TEMPORARY RAMP C													
604+41.39	604+50.00	0.0	0.0	0.0	4.3	0.0	1.4	0.0	0.0	0.0	13.8	0.0	-13.8
604+50.00	605+00.00	0.0	0.0	0.0	63.0	0.0	30.0	0.0	0.0	0.0	318.7	0.0	-318.7
605+00.00	605+50.00	0.0	0.0	0.0	94.4	0.0	78.1	0.0	0.0	0.0	559.3	0.0	-559.3
605+50.00	606+00.00	0.0	0.0	0.0	106.5	0.0	106.5	0.0	0.0	0.0	574.0	0.0	-574.0
606+00.00	606+50.00	0.0	0.0	0.0	92.8	0.0	92.8	0.0	0.0	0.0	409.9	0.0	-409.9
606+50.00	607+00.00	0.0	0.0	0.0	71.4	0.0	42.5	0.0	0.0	0.0	175.7	0.0	-175.7
607+00.00	607+50.00	0.0	0.2	0.0	62.2	0.0	0.0	0.0	0.1	0.0	56.3	0.0	-56.1
607+50.00	608+00.00	0.0	13.4	0.0	53.9	0.0	0.0	0.0	11.4	0.0	68.2	0.0	-56.8
608+00.00	608+50.00	0.0	24.4	0.0	35.2	0.0	0.0	0.0	20.7	0.0	34.3	0.0	-13.6
608+50.00	609+00.00	0.0	11.1	0.0	37.1	0.0	0.0	0.0	9.4	0.0	51.4	0.0	-42.0
609+00.00	609+50.00	0.0	0.0	0.0	51.5	0.0	0.0	0.0	0.0	0.0	112.2	0.0	-112.2
609+50.00	610+00.00	0.0	3.9	0.0	60.6	0.0	0.0	0.0	3.3	0.0	130.2	0.0	-126.9
610+00.00	610+50.00	0.0	3.9	0.0	65.4	0.0	0.0	0.0	3.3	0.0	136.1	0.0	-132.8
610+50.00	611+00.00	0.0	0.0	0.0	63.2	0.0	0.0	0.0	0.0	0.0	137.6	0.0	-137.6
611+00.00	611+50.00	0.0	0.0	0.0	60.6	0.0	0.0	0.0	0.0	0.0	143.9	0.0	-143.9
611+50.00	612+00.00	0.0	0.0	0.0	62.2	0.0	0.0	0.0	0.0	0.0	151.9	0.0	-151.9
612+00.00	612+50.00	0.0	0.0	0.0	57.9	0.0	0.0	0.0	0.0	0.0	151.6	0.0	-151.6
612+50.00	612+88.70	0.0	0.0	0.0	20.9	0.0	0.0	0.0	0.0	0.0	58.8	0.0	-58.8
612+88.70	END												
	SUB-TOTAL	0.0	56.8	0.0	1063.0	0.0	351.3	0.0	48.3	0.0	3283.8	0.0	-3235.5
TEMPORARY RAMP D													
700+31.69	700+50.00	15.6	0.0	23.0	0.0	0.0	0.0	13.3	0.0	6.6	0.0	6.7	0.0
700+50.00	701+00.00	107.1	0.0	108.4	0.0	0.0	0.0	91.0	0.0	34.5	0.0	56.5	0.0
701+00.00	701+50.00	96.5	0.0	110.2	0.0	0.0	0.0	82.1	0.0	41.0	0.0	41.1	0.0
701+50.00	702+00.00	42.7	0.0	107.4	0.0	0.0	0.0	36.3	0.0	47.6	0.0	-11.3	0.0
702+00.00	702+50.00	11.9	0.0	70.0	0.0	0.0	0.0	10.2	0.0	48.7	0.0	-38.6	0.0
702+50.00	703+00.00	2.3	0.0	41.1	0.0	0.0	0.0	2.0	0.0	41.3	0.0	-39.3	0.0
703+00.00	703+50.00	2.0	0.0	22.3	0.0	0.0	0.0	1.7	0.0	21.8	0.0	-20.1	0.0
703+50.00	704+00.00	1.7	0.0	15.9	0.0	0.0	0.0	1.4	0.0	11.1	0.0	-9.7	0.0
704+00.00	END												
	SUB-TOTAL	279.9	0.0	498.3	0.0	0.0	0.0	237.9	0.0	252.5	0.0	-14.6	0.0
GRAND TOTAL:		316.5	56.8	1967.6	1063.0	0.0	351.3	269.0	48.3	8093.7	3283.8	-7824.7	-3235.5

NOTE: SEE GENERAL NOTES SHEET 3 FOR TEMPORARY PAVEMENT INFORMATION.

\FS-8044\VAHV\VAULT.T.D-TRANS.DT\2202\21379-801\CIVIL\CAD\60445\ASHEET.DWG\60445-SHT-SCHEDULE.LDGN
 STANKIRJ
 12-12-2011 17:59:30
 *D:\60445-80445\60445.DGN

FILE NAME =	USER NAME = *USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 345 / US ROUTE 20	SCHEDULE OF QUANTITIES - XI EARTHWORK SCHEDULES TEMPORARY RAMPS - STAGES IA AND IIA			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - MRK	REVISED -		345	8R-R	KANE	794	49			
	PLOT SCALE = *SCALE#	CHECKED - DDH	REVISED -		CONTRACT NO. 60445							
	PLOT DATE = *DATE#	DATE - 12/16/11	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	

