

EARTHWORK SCHEDULE

STA FROM	TO STA	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	PGES PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
MCLEAN TEMP WIDENING							
58+50.00	59+00.00	0.0	23.6	0.0	0.0	15.4	-15.4
59+00.00	59+50.00	0.1	35.7	0.0	0.1	18.0	-17.9
59+50.00	59+73.25	0.1	19.8	0.0	0.1	8.3	-8.2
59+73.25	60+00.00	0.1	25.5	0.0	0.1	16.6	-16.5
60+00.00	60+50.00	0.1	48.9	0.0	0.1	40.6	-40.6
60+50.00	61+00.00	1.0	49.2	0.0	0.8	37.0	-36.2
61+00.00	61+50.00	6.7	42.2	0.0	5.7	23.0	-17.3
61+50.00	62+00.00	11.1	36.9	0.0	9.4	27.1	-17.6
62+00.00	62+50.00	10.2	36.1	0.0	8.7	32.6	-24.0
62+50.00	63+00.00	18.1	33.7	0.0	15.4	13.2	2.1
63+00.00	63+50.00	41.8	37.0	0.0	35.5	2.7	32.9
63+50.00	64+00.00	41.2	38.4	0.0	35.0	2.9	32.1
64+00.00	64+50.00	17.0	29.1	0.0	14.4	3.1	11.3
64+50.00	65+50.00	14.9	50.8	0.0	12.7	7.4	5.3
65+50.00	66+00.00	7.9	29.4	0.0	6.7	4.6	2.0
66+00.00	66+50.00	15.0	29.3	0.0	12.8	3.5	9.2
66+50.00	67+00.00	21.3	28.5	0.0	18.1	2.4	15.7
67+00.00	67+50.00	20.5	27.6	0.0	17.5	2.5	15.0
67+50.00	68+00.00	18.7	13.6	0.0	15.9	3.1	12.8
68+00.00	68+50.00	18.4	12.1	0.0	15.7	2.7	13.0
68+50.00	69+00.00	11.3	26.2	0.0	9.6	7.3	2.4
69+00.00	69+50.00	6.6	38.8	0.0	5.6	11.2	-5.6
69+50.00	70+00.00	5.9	47.7	0.0	5.0	18.9	-13.9
70+00.00	70+50.00	2.9	46.1	0.0	2.4	26.6	-24.2
70+50.00	71+00.00	4.3	45.5	0.0	3.6	20.7	-17.0
71+00.00	71+50.00	6.9	54.1	0.0	5.8	30.3	-24.5
71+50.00	72+00.00	32.9	31.6	0.0	28.0	22.3	5.7
72+00.00	72+50.00	45.1	42.7	0.0	38.3	3.1	35.2
72+50.00	73+00.00	49.4	75.5	0.0	42.0	3.8	38.3
73+00.00	73+50.00	35.4	32.8	0.0	30.1	0.9	29.2
73+50.00	74+00.00	4.1	0.0	0.0	3.5	0.2	3.3
74+00.00	74+50.00	5.4	0.0	0.0	4.5	0.2	4.3
74+50.00	75+00.00	7.6	0.0	0.0	6.5	0.2	6.3
75+00.00	75+50.00	12.2	23.4	0.0	10.3	7.5	2.9
75+50.00	76+00.00	13.5	63.6	0.0	11.5	78.0	-66.4
76+00.00	77+00.00	17.8	80.5	0.0	15.1	141.8	-126.6
77+00.00	77+50.00	7.9	12.2	0.0	6.7	1.6	5.1
77+50.00	78+00.00	7.4	23.0	0.0	6.3	2.5	3.8
78+00.00	78+50.00	11.2	22.6	0.0	9.5	1.8	7.7
78+50.00	78+78.00	14.8	6.6	0.0	12.6	0.4	12.2
78+78.00	79+00.00	12.5	0.0	0.0	10.6	0.6	10.0
79+00.00	79+50.00	25.3	6.4	0.0	21.5	1.5	20.0
79+50.00	80+00.00	42.2	6.4	0.0	35.9	0.3	35.6
80+00.00	80+50.00	44.8	4.0	0.0	38.1	0.3	37.7
80+50.00	81+00.00	36.1	4.0	0.0	30.7	1.8	28.8
81+00.00	81+50.00	37.5	0.0	0.0	31.9	3.3	28.6
81+50.00	82+00.00	36.5	0.0	0.0	31.0	2.3	28.7
82+00.00	82+50.00	38.0	0.0	0.0	32.3	0.8	31.5
82+50.00	83+50.00	86.3	8.5	0.0	73.4	0.5	72.8
83+50.00	84+00.00	39.6	9.1	0.0	33.7	0.3	33.3
84+00.00	84+50.00	32.3	10.1	0.0	27.5	0.3	27.1
84+50.00	85+00.00	29.8	10.9	0.0	25.4	0.3	25.0
85+00.00	85+50.00	31.1	5.6	0.0	26.5	0.2	26.2
85+50.00	86+00.00	33.0	0.0	0.0	28.1	0.2	27.9
86+00.00	86+50.00	26.4	0.0	0.0	22.5	0.8	21.7
86+50.00	86+70.00	7.6	0.0	0.0	6.5	0.5	6.0
86+70.00	87+00.00	8.7	0.0	0.0	7.4	0.5	7.0
87+00.00	87+50.00	6.3	5.6	0.0	5.4	1.2	4.1
87+50.00	88+00.00	1.5	5.6	0.0	1.3	2.3	-1.0
88+00.00	END						
	SUB-TOTAL	1142.7	1396.6	0.0	971.3	664.1	307.2

STA FROM	TO STA	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	PGES PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1	STAGE II.1
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
LILLIAN TEMP WIDENING							
200+50.00	201+00.00	150.6	28.7	0.0	128.0	1.6	126.4
201+00.00	201+39.02	106.3	11.8	0.0	90.3	1.3	89.0
201+39.02	201+50.00	26.6	2.7	0.0	22.6	0.1	22.4
201+50.00	202+00.00	50.2	17.5	0.0	42.7	2.3	40.4
202+00.00	202+50.00	30.2	16.7	0.0	25.7	4.7	21.0
202+50.00	203+00.00	17.3	11.7	0.0	14.7	3.3	11.4
203+00.00	203+50.00	4.9	6.2	0.0	4.2	0.4	3.8
203+50.00	END						
	SUB-TOTAL	386.0	95.2	0.0	328.1	13.7	314.4
	GRAND TOTAL	1528.6	1491.8	0.0	1299.4	677.8	621.5

NOTE: SEE GENERAL NOTES SHEET 3 FOR TEMPORARY PAVEMENT INFORMATION.

FILE NAME = \\FS-0204\AMVAV\VAULT\T.D. TRANS. 07\AZ2002\21379-000\1\CIVIL\LOAD\G0H45\SHEET\0160H45-SHT - SCHEDULE12.DGN
 STANKIRJ
 12-12-2011 17:59:33
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 345 / US ROUTE 20	SCHEDULE OF QUANTITIES - XII EARTHWORK SCHEDULES MCLEAN AND LILLIAN TEMP PAVEMENT - STAGE II.1			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - MRK	REVISED -		345	8R-R	KANE	794	50			
PLOT SCALE = #SCALE#		CHECKED - DDH	REVISED -		CONTRACT NO. 60H45							
PLOT DATE = #DATE#		DATE - 12/16/11	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	