



\\F5-0014\MY\VAULT\J.D. TRAVIS.B7\2202-12179-001\CIVIL\CAD\60H45\SHEET\0160H45-SHT-STAGING\06.DGN
 \\F5-0014\MY\VAULT\J.D. TRAVIS.B7\2202-12179-001\CIVIL\CAD\60H45\SHEET\0160H45-SHT-STAGING\06.DGN
 \\F5-0014\MY\VAULT\J.D. TRAVIS.B7\2202-12179-001\CIVIL\CAD\60H45\SHEET\0160H45-SHT-STAGING\06.DGN
 \\F5-0014\MY\VAULT\J.D. TRAVIS.B7\2202-12179-001\CIVIL\CAD\60H45\SHEET\0160H45-SHT-STAGING\06.DGN




FILL GAP BETWEEN BOTTOM OF TEMP PAVEMENT AND TOP OF STABILIZED SUBBASE WITH STABILIZED SUBBASE, TEMPORARY PAVEMENT, OR LEVELING BINDER. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TEMPORARY PAVEMENT.

STAGE IC TYPICAL SECTION A-A
 US ROUTE 20
 STA. 78+50 TO STA. 79+50



FILL GAP BETWEEN BOTTOM OF TEMP PAVEMENT AND TOP OF STABILIZED SUBBASE WITH STABILIZED SUBBASE, TEMPORARY PAVEMENT, OR LEVELING BINDER. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TEMPORARY PAVEMENT.

STAGE IC TYPICAL SECTION B-B
 US ROUTE 20
 STA. 79+85 TO STA. 83+50



FILL GAP BETWEEN BOTTOM OF TEMP PAVEMENT AND TOP OF STABILIZED SUBBASE WITH STABILIZED SUBBASE, TEMPORARY PAVEMENT, OR LEVELING BINDER. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TEMPORARY PAVEMENT.

STAGE IC TYPICAL SECTION C-C
 US ROUTE 20
 STA. 83+50 TO STA. 84+50

- NOTES:**
- THE TEMPORARY CONCRETE BARRIER SHALL BE SECURED TO THE PAVEMENT USING THREE ANCHORING PINS ON THE TRAFFIC SIDE OF THE BARRIER AT LOCATIONS WHERE A HAZARD OR SLOPE STEEPER THAN 1V:10H EXISTS WITHIN 3 FT OF THE BARRIER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR "TEMPORARY CONCRETE BARRIER", OR "RELOCATE TEMPORARY CONCRETE BARRIER" (AS APPLICABLE).
 - THE TEMPORARY CONCRETE BARRIER BETWEEN OPPOSING LANES OF TRAFFIC SHALL BE CENTERED BETWEEN THE LANE LINES OR AS SHOWN ON THE PLANS.
 - TEMPORARY PAVEMENT ON US ROUTE 20 AND RAMPS SHALL BE ACCORDING TO THE PAVEMENT STRUCTURE DETAILS AND MIX DESIGN REQUIREMENTS ON THE TYPICAL SECTIONS SHEET 38.

LEGEND

- TEMPORARY CONCRETE BARRIER
- VERTICAL PANELS WITH FLASHING LIGHT
- DRUM OR BARRICADE WITH FLASHING LIGHT
- DIRECTION OF TRAFFIC
- TEMPORARY PAVEMENT (SEE NOTE 5)

- ① WET REFLECTIVE TEMPORARY TAPE TYPE III - LINE 4" WHITE
- ② WET REFLECTIVE TEMPORARY TAPE TYPE III - LINE 4" YELLOW
- ③ WET REFLECTIVE TEMPORARY TAPE TYPE III - LINE 4" WHITE (2' DASH - 6' SKIP)
- ④ WET REFLECTIVE TEMPORARY TAPE TYPE III - LINE 4" WHITE (10' DASH - 30' SKIP)
- ⑤ WET REFLECTIVE TEMPORARY TAPE TYPE III - LINE 8" WHITE
- ⑥ MODULAR GLARE SCREEN SYSTEM

FILE NAME =	USER NAME = *USER*	DESIGNED - MM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGING AND TRAFFIC CONTROL U.S. ROUTE 20 TYPICAL SECTIONS STAGE IC	F.A.P. RTE. 345	SECTION 8R-R	COUNTY KANE	TOTAL SHEETS 794	SHEET NO. 130
#FILEL#		DRAWN - RJS	REVISED -	FAP ROUTE 345 / US ROUTE 20	SCALE: 1"=10'	SHEET NO.	OF	STA.	TO STA.	CONTRACT NO. 60H45
PLOT SCALE = *SCALE*		CHECKED - PB	REVISED -							FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT
PLOT DATE = *DATE*		DATE - 12/16/11	REVISED -							

