

**SUMMARY OF QUANTITIES**

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE REPLACEMENT 0011
54213471	END SECTIONS 36"	EACH	1	1	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	63	63	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	131	131	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	8	8	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	33	33	
55100500	STORM SEWER REMOVAL 12"	FOOT	86	86	
55100700	STORM SEWER REMOVAL 15"	FOOT	134	134	
55100900	STORM SEWER REMOVAL 18"	FOOT	12	12	
55101600	STORM SEWER REMOVAL 36"	FOOT	24	24	
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60500040	REMOVING MANHOLES	EACH	2	2	
60500050	REMOVING CATCH BASINS	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	811	811	
60604310	COMBINATION CONCRETE CURB AND GUTTER, TYPE SB-6.12	FOOT	646	646	
60605567	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-8.12	FOOT	91	91	
60618210	HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH	SQ FT	962	962	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50.0	50.0	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	

\* INDICATES SPECIALTY ITEMS

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE REPLACEMENT 0011
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	507	507	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	650	650	
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	128	128	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2714	2714	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	262.5	262.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	262.5	262.5	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	219	219	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3921	3921	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	726	726	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	20	20	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	121	121	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2059	2059	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	121	121	
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	299	299	
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2404	2404	

\* INDICATES SPECIALTY ITEMS

FILE NAME = ...\\D160M83-ah-t-S002-PostF inal.dgn



DESIGNED - RJD	REVISED -
DRAWN - GEW	REVISED -
CHECKED - RJD	REVISED -
DATE - 12/12/2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 53 OVER ST JOSEPH'S CREEK**  
**SUMMARY OF QUANTITIES**

SCALE: N/A      SHEET NO. 2 OF 3 SHEETS      STA.      TO STA.

F.A.P. RTE. 870	SECTION 534R-B	COUNTY	TOTAL SHEETS 51	SHEET NO. 4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60M83	