

**SUMMARY OF QUANTITIES**

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE REPLACEMENT 0011
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2378	2378	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	328	328	
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	163	163	
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2056	2056	
* A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALIPER, BALLED AND BURLAPPED	EACH	12	12	
X0324719	CHECK VALVE 18"	EACH	1	1	
* X2502014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.50	0.50	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	7831	7831	
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	52	52	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	774	774	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	352	352	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0028462	GEOTEXTILE RETAINING WALL	SQ FT	115		115
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
Z0062456	TEMPORARY PAVEMENT	SQ YD	357	357	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	444		444
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1	
Z0038137	THREE-SIDED PRECAST CONCRETE STRUCTURES 28'X 10'	FOOT	83.3		83.3

\* INDICATES SPECIALTY ITEMS