

CONSTRUCTION CODE  
 URBAN FEDERAL 90% STATE 10%

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	82	82
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	32	32
20200100	EARTH EXCAVATION	CU YD	1,081	1,081
* 20200200	ROCK EXCAVATION	CU YD	4,000	4,000
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	781	781
20400800	FURNISHED EXCAVATION	CU YD	201	201
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	48,100	48,100
25000210	SEEDING, CLASS 2A	ACRE	1.2	1.2
25000310	SEEDING, CLASS 4	ACRE	8.8	8.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	110	110
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110	110
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	110	110
25100115	MULCH, METHOD 2	ACRE	4.3	4.3
25100135	MULCH, METHOD 4	ACRE	10.0	10.0
25100630	EROSION CONTROL BLANKET	SQ YD	27,700	27,700
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,000	1,000
28000305	TEMPORARY DITCH CHECKS	FOOT	990	990
28000400	PERIMETER EROSION BARRIER	FOOT	2,200	2,200
28100101	STONE RIPRAP, CLASS A1	SQ YD	100	100
28200200	FILTER FABRIC	SQ YD	100	100
<b>40201000</b>	<b>AGGREGATE FOR TEMPORARY ACCESS</b>	<b>TON</b>	<b>239</b>	<b>239</b>
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	140	140
<b>54210024</b>	<b>PIPE CULVERTS, CLASS D, TYPE 1, 24" (TEMPORARY)</b>	<b>FOOT</b>	<b>60</b>	<b>60</b>
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	210	210
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	61	61

\* Specialty Items

n:\p\01\00003384\_08\6\_high\_mast\mast\design\proposed.pln\3384\_6\_US30\_High\_Mast\_03-S00201.dgn

**ENGINEERING CONSULTANT**  
**Corba Group, Inc.**  
 CONSULTING ENGINEERS  
 2302 North Cumberland Avenue, Suite 402  
 Chicago, IL 60614  
 Tel: 773.775.4500 Fax: 773.775.4914  
 Email: chicago@corba.com

USER NAME = wjancaster	DESIGNED - RJR	REVISED -
PLOT SCALE = 2.0000' / 1"	DRAWN - RJR	REVISED -
PLOT DATE = 2/14/2012	CHECKED - JMV	REVISED -
	DATE - 02-14-2012	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 80 AT U.S. ROUTE 30 LIGHTING  
 SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	2011-046-L	WILL	106	4
CONTRACT NO. 60P56			ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.