

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|------------|---|-----------------|----------------|--------------------------------|-------------|
| | | | | URBAN - 90% FEDERAL, 10% STATE | SAFETY 0021 |
| * Z0007118 | UNTREATED TIMBER LAGGING | SQ FT | 1,357 | 1,357 | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | |
| * Z0026402 | FURNISHING SOLDIER PILES (HP SECTION) | FOOT | 1,077 | 1,077 | |
| Z0030260 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 5 | 5 | |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 103 | 103 | |
| Z0033028 | MAINTENANCE OF LIGHTING SYSTEM | CAL MO | 13 | 13 | |
| Z0033052 | COMMUNICATIONS VAULT | EACH | 3 | 3 | |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | |
| Z0064800 | SELECTIVE CLEARING | UNIT | 85 | 85 | |
| | DITCH CROSS-OVER | EACH | 2 | 2 | |
| 81603032 | UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE | FOOT | 5,800 | 5,800 | |
| 82500420 | LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 200 AMP (DUAL) | EACH | 1 | 1 | |
| 87101024 | FIBER OPTIC CABLE, ON MESSENGER SINGLE MODE, NO. 62.5/125, 24 FIBERS | FOOT | 1,450 | 1,450 | |

| | | | | | |
|----------|--|-------|------|------|--|
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N 70 | TON | 90 | 90 | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL 2" | SQ YD | 780 | 780 | |
| 54213459 | END SECTIONS 24" | EACH | 4 | 4 | |
| 64200116 | SHOULDER RUMBLE STRIPS, 16 INCH | FOOT | 5250 | 5250 | |
| 70300560 | PAVEMENT MARKING TAPE, TYPE III 12" | FOOT | 370 | 370 | |
| 78003110 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" | FOOT | 130 | 130 | |
| 78003120 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5" | FOOT | 1400 | 1400 | |
| X0324237 | CLOSED CIRCUIT TELEVISION DOME CAMERA HIGH MAST TOWER INSTALLATION | EACH | 5 | 5 | |
| X7030045 | WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH | FOOT | 4000 | 4000 | |
| X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 1530 | 1530 | |
| Z0055905 | TEMPORARY CONSTRUCTION FENCE | FOOT | 505 | 505 | |

* Specialty Items Rev.

ENGINEERING CONSULTANT
Corba Group, Inc.
 CONSULTING ENGINEERS
 5917 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60636
 Tel: 773.776.8200 Fax: 773.776.4014
 Email: chicago@corba.com

| | | |
|----------------------------|-------------------|-----------|
| USER NAME = wlencoaster | DESIGNED - RJR | REVISED - |
| PLOT SCALE = 2.0000' / IN. | DRAWN - RJR | REVISED - |
| PLOT DATE = 2/14/2012 | CHECKED - JMV | REVISED - |
| | DATE - 02-14-2012 | REVISED - |

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 80 AT U.S. ROUTE 30 LIGHTING
 SUMMARY OF QUANTITIES

| | | | | | |
|--------|-----------|----|--------|------|---------|
| SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. |
|--------|-----------|----|--------|------|---------|

| | | | | |
|--------------------|------------|--------|---------------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 80 | 2011-046-L | WILL | 106 | 8 |
| CONTRACT NO. 60P56 | | | ILLINOIS FED. AID PROJECT | |

m:\p\0\100603384\201-6_high_mast\design\proposed_plan\3884_6_US30_high_mast_03-30-08.dgn