

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE 0014				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0014					
42001300	PROTECTIVE COAT	SO YD	1886	1886					
50102400	CONCRETE REMOVAL	CU YD	95.1	95.1					
50157300	PROTECTIVE SHIELD	SO YD	849	849					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	185	185					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	30,900	30,900					
50901730	BRIDGE FENCE RAILING	FOOT	472	472					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	344	344					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5					
* 72000200	SIGN PANEL - TYPE 2	SQ FT	24	24					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	129	129					
78300100	PAVEMENT MARKING REMOVAL	SO FT	43	43					
X2011000	TEMPORARY FENCE (SPECIAL)	FOOT	28	28					
* Specialty Items									

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE 0014				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0014					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	1032	1032					
Z0001905	STRUCTURAL STEEL REPAIR	POUND	1070	1070					
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	900	900					
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	48	48					
Z0021914	SILICONE JOINT SEALER, 2.75"	FOOT	145	145					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					

FILE NAME = c:\pwworkspace\curryw\02288452\0162211-Design.dwg	USER NAME = curryw	DESIGNED -	REVISED -
PLOT SCALE = 100:1=08' / 1in.		DRAWN -	REVISED -
PLOT DATE = 3/15/2012		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE. 94	SECTION 2011-066-1	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P85	

Rev.