

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	0014 LOCATION 1 ASHLAND COOK COUNTY
CODE NO.	ITEM	UNIT		
20300100	CHANNEL EXCAVATION	CU YD	45	45
28100107	STONE RIPRAP, CLASS A4	SQ YD	385	385
28200200	FILTER FABRIC	SQ YD	1,290	1,290
28400100	GABIONS	CU YD	58	58
28401000	SLOPE MATTRESS 12"	SQ YD	777	777
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4

COMPANY NAME: #COMPANY NAME
 PROJECT CONTACT: #PROJECT CONTACT
 CLIENT: #CLIENT
 DATE PLOTTED: 2/15/2012 4:23:35 PM
 FILE NAME: B6100196.03-60R55-sum.dgn
 PLOT DRIVER: pdf.plt
 PEN TABLE: standard.ctb



USER NAME = JGuerr	DESIGNED - C. HARTKE	REVISED -
	DRAWN - S. PERNAL	REVISED -
PLOT SCALE = N/A	CHECKED - T. HAMILTON	REVISED -
PLOT DATE = 2/15/2012	DATE - 2/15/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2857	2011-214-1	COOK	12	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60R55	