

SUMMARY OF QUANTITIES

				IL ROUTE 72 @ STATE ST./GETZELMAN RD.	
LOCATION OF WORK			CONSTRUCTION CODE		0021
SUMMARY OF QUANTITIES			GRAND		90% Fed
CODE NO.	ITEM	UNIT	TOTAL	10% Village	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
72000100	SIGN PANEL - TYPE 1	SQ FT	31.5	31.5	
72000200	SIGN PANEL - TYPE 2	SQ FT	32.5	32.5	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	300	300	
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	597	597	
81400100	HANDHOLE	EACH	5	5	
81400200	HEAVY-DUTY HANDHOLE	EACH	1	1	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	
87200400	SPAN WIRE	FOOT	350	350	
87200500	TETHER WIRE	FOOT	350	350	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	927	927	
87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	552	552	
87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	1,102	1102	
87302505	ELECTRIC CABLE AERIAL SUSPENDED, SERVICE, NO. 6 2 C	FOOT	72	72	
87302650	ELECTRIC CABLE AERIAL SUSPENDED, LEAD-IN, NO. 14 1 PAIR	FOOT	785	785	
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	8	
88600100	DETECTOR LOOP, TYPE I	FOOT	917	917	
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1	1	
X0326133	TEMPORARY WOOD POLE, 45 FEET, CLASS 5	EACH	4	4	
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1	1	
X8800025	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	4	4	
X8800046	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, SPAN WIRE MOUNTED	EACH	8	8	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	