F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	112R-N	McHENRY	266	207
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62537				

FINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE

ORIGINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE

112+25.05

874.94 -1.50 % 874.82 -2.00 % 874.30 2.00% 6.00%

EX ROW — COMMERCIAL CONCRETE ENTRANCE — ESMT.

30" S.S.

	CUT(SF)	FILL(SF)
PRESTAGE:	4.23	0.00
STAGE-1:	49.50	3.59
STAGE-2:	20.67	3.28
STAGE-3:	21.68	0.00

EX ROW — 874.4 -2.00 % 874.22 -2.00 % 874.74 -1.50 % 874.87 874.83 -1.50 % 874.74 -2.00 % 874.21 2.00% 872.7

EX ROW

10" WATER

112+00.00

12" SANITARY

30" S.S.

874.91 874.77 -1.50 % 874.75 -2.00 % 874.23 4.90%

COMMERCIAL CONCRETE ENTRANCE — EX ROW

30" S.S.

111+11.07

LEGEND

- TEMPORARY PAVEMENT
- TEMPORARY AGGREGATE SHOULDER
- EXCAVATION OF UNSUITABLE SOIL AND REPLACEMENT WITH POROUS GRANULAR EMBANKMENT, SUBGRADE
- PAVEMENT REMOVAL