

Specialty Item	Special Provision	Item No	Description	Unit	Total Quantity	HPP FUNDING				STU FUNDING			
						Construction Code 003	Construction Code 0004	Construction Code 0005	Construction Code 0021	Construction Code 003	Construction Code 0004	Construction Code 0005	Construction Code 0021
						McCARTHY ROAD	DERBY ROAD	ARCHER AVENUE	TRAFFIC SIGNALS	McCARTHY ROAD	DERBY ROAD	ARCHER AVENUE	TRAFFIC SIGNALS
		54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1	0.2				0.8			
		54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	0.2				0.8			
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	910	124.3	18.9			665.7	101.1		
		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	58	9.1				48.9			
		550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	157	24.7				132.3			
		550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	104	16.4				87.6			
		550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	39	6.1				32.9			
		550A0330	STORM SEWERS, CLASS A, TYPE 2 10"	FOOT	4	0.6				3.4			
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	212	22.7	10.7			121.3	57.3		
		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	499	60.7	17.8			325.3	95.2		
		550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	705	59.8	51.1			320.2	273.9		
		550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	508	79.9				428.1			
		550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	287	45.1				241.9			
		55100400	STORM SEWER REMOVAL 10"	FOOT	28	4.4				23.6			
		55100500	STORM SEWER REMOVAL 12"	FOOT	345	54.3				290.7			
		55100700	STORM SEWER REMOVAL 15"	FOOT	414		65.1				348.9		
		55100900	STORM SEWER REMOVAL 18"	FOOT	259	40.7				218.3			
		55101100	STORM SEWER REMOVAL 21"	FOOT	408	64.2				343.8			
		55101200	STORM SEWER REMOVAL 24"	FOOT	267	42.0				225.0			
	SP	56106700	ADJUSTING WATER MAIN 16"	FOOT	30	4.7				25.3			
		56300300	ADJUSTING WATER SERVICE LINES	FOOT	140	22.0				118.0			
*		56400100	FIRE HYDRANTS TO BE MOVED	EACH	5	0.8				4.2			
		60107600	PIPE UNDERDRAINS 4"	FOOT	360	31.5	25.2			168.5	134.8		
		60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5	0.8				4.2			
		60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	36	4.4	1.3			23.6	6.7		
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	0.9	0.2			5.1	0.8		
		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14	1.6	0.6			8.4	3.4		
		60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0.2				0.8			
		60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	0.6	0.3			3.4	1.7		
		60255500	MANHOLES TO BE ADJUSTED	EACH	15	1.4	0.9			7.6	5.1		
		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6	0.8	0.2			4.2	0.8		
		60500040	REMOVING MANHOLES	EACH	1	0.2				0.8			
		60500050	REMOVING CATCH BASINS	EACH	11	1.6	0.2			8.4	0.8		
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	781	87.3	35.5			467.7	190.5		
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6094	725.9	211.7	20.9		3889.1	1134.3	112.1	
*		63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	150	23.6				126.4			
*		63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	0.6				3.4			
*	SP	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2710	347.6	47.2	31.5		1862.4	252.8	168.5	
*	SP	66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	8500.1	1101.1		236.0		5898.9		1264.1	
*	SP	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	0.2				0.8			
*	SP	66900530	SOIL DISPOSAL ANALYSIS	EACH	6	0.6	0.2	0.2		3.4	0.8	0.8	
*	SP	66901000	BACKFILL PLUGS	CU YD	65	10.2				54.8			
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	0.9	0.9			5.1	5.1		
		67100100	MOBILIZATION	L SUM	1	0.1	0.1			0.4	0.4		
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.1	0.1			0.4	0.4		
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.1	0.1			0.4	0.4		
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.1	0.1			0.4	0.4		
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	40	2.5	2.5	1.3		13.5	13.5	6.7	
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	604	76.8	18.2			411.2	97.8		

Frank Novotny & Associates, Inc.
 835 Midway Drive • Willowbrook, IL • 60527 • Telephone: (630) 887-9660 • Fax: (630) 887-0132
 ILLINOIS PROFESSIONAL DESIGN FIRM NO. 154-000288

FILE NAME = FAU 1587 (McCARTHY ROAD)
 FAP 577 (ARCHER AVENUE)
 FAU 1024 (DERBY ROAD)
 CHANNELIZATION AND
 TRAFFIC SIGNAL INSTALLATION

USER NAME =
 PLOT SCALE =
 PLOT DATE =

DESIGNED -- JLC
 DRAWN -- JFP
 CHECKED -- THK
 DATE -- 11/10

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	02-00055-00-WR	COOK	84	5
CONTRACT NO. 63557				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HPP-M-8003(504)				