

SUMMARY OF QUANTITIES				ROADWAY	SAFETY	TRAINEES	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		
					0004	0021	0042
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100		
	20800150	TRENCH BACKFILL	CU YD	126	126		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2200	2200		
	28000400	PERIMETER EROSION BARRIER	FOOT	360	360		
	28000510	INLET FILTERS	EACH	12	12		
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	2008	2008		
	35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	1320	1320		
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	203	203		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1575	1575		
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	250	250		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	191	191		
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	740	740		
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	661	661		
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50	50		
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6030		6030	
	42400800	DETECTABLE WARNINGS	SQ FT	128		128	
	44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	3526	3526		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1679	1679		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2560	2560		
	44000600	SIDEWALK REMOVAL	SQ FT	3085	3085		
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	25	25		
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	139	139		
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2376	2376		
	542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	15	15		
	550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	9	9		
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	468	468		

* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES				ROADWAY	SAFETY	TRAINEES	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		
					0004	0021	0042
	55100300	STORM SEWER REMOVAL 8"	FOOT	74	74		
	55100400	STORM SEWER REMOVAL 10"	FOOT	297	297		
	55100500	STORM SEWER REMOVAL 12"	FOOT	45	45		
	56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	2	2		
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	6	6		
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1		
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5		
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	20	20		
	60500040	REMOVING MANHOLES	EACH	2	2		
	60500050	REMOVING CATCH BASINS	EACH	7	7		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2607	2607		
	60624600	CORRUGATED MEDIAN	SQ FT	40	40		
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	480	480		
*	66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	18000	18000		
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1		
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3		
*	66901000	BACKFILL PLUGS	CU YD	10	10		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
	67100100	MOBILIZATION	L SUM	1	1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8		8	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	860		860	
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2596		2596	
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	85		85	
*	72000100	SIGN PANEL - TYPE 1	SQ FT	131		131	
*	72000200	SIGN PANEL - TYPE 2	SQ FT	95		95	

* - INDICATES SPECIALTY ITEMS

FILE NAME = 09027-QUAN-01 - P01

USER NAME =	DESIGNED -- HLG	REVISED --
PLOT SCALE =	CHECKED -- HLG	REVISED --
PLOT DATE = 02-22-12	DRAWN -- LTL	REVISED --
	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 0344 (127TH STREET) AT SACRAMENTO AVENUE SUMMARY OF QUANTITIES AND GENERAL NOTES	
SCALE: NA	SHEET NO. 3 OF 48 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0344	06-00175-00-TL	COOK	48	3
CONTRACT NO. 63613				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				