

SUMMARY OF QUANTITIES					ROADWAY	SAFETY	TRAINEES
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		
					0004	0021	0042
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	225		225	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	170		170	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4470		4470	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	565		565	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	595		595	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	250		250	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	124		124	
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	110		110	
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	116		116	
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1	
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1	
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1	
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	593		593	
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	490		490	
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	109		109	
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	207		207	
*	81400100	HANDHOLE	EACH	6		6	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	2		2	
*	81400300	DOUBLE HANDHOLE	EACH	2		2	
*	81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2800		2800	
*	81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	60		60	
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	17		17	
*	82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1		1	
*	83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	17		17	
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	170		170	

* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES					ROADWAY	SAFETY	TRAINEES
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		
					0004	0021	0042
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	17		17	
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	6		6	
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	6		6	
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1077		1077	
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1171		1171	
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1545		1545	
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	699		699	
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1163		1163	
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	101		101	
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	411		411	
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2		2	
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2	
*	87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	1		1	
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1	
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
*	87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1		1	
*	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1	
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		20	
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60		60	
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		8	
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2	
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2	
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8	

* - INDICATES SPECIALTY ITEMS

FILE NAME = 0927-QUAN-01 - P02

USER NAME =	DESIGNED -- HLG	REVISED --
PLOT SCALE =	CHECKED -- HLG	REVISED --
PLOT DATE = 02-22-12	DRAWN -- LTL	REVISED --
	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 0344 (127TH STREET)
AT SACRAMENTO AVENUE
SUMMARY OF QUANTITIES AND GENERAL NOTES

SCALE: NA SHEET NO. 4 OF 48 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0344	06-00175-00-TL	COOK	48	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 63613				