

SUMMARY OF QUANTITIES

CARPENTER STREET				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
20101200	TREE ROOT PRUNING	EACH	5	5
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	110	110
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
25200110	SODDING, SALT TOLERANT	SQ YD	110	110
25200200	SUPPLEMENTAL WATERING	UNIT	5	5
28000510	INLET FILTERS	EACH	16	16
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	460	460
40600300	AGGREGATE (PRIME COAT)	TON	9	9
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	199	199
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	181	181
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	398	398
42001300	PROTECTIVE COAT	SQ YD	320	320
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	55	55
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	520	520

CARPENTER STREET				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005
42400800	DETECTABLE WARNINGS	SQ FT	88	88
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,600	4,600
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	70	70
44000600	SIDEWALK REMOVAL	SQ FT	520	520
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	355	355
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	100	100
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	100	100
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	120	120
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	150	150
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	355	355
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	25	25
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	15	15
X6030310	FRAME AND LIDS TO BE ADJUSTED, SPECIAL	EACH	19	19
X2800510	INLET FILTER CLEANING	EACH	17	17

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME - USER	DESIGNED - SAV	REVISED
FILE NAME =		DRAWN - SAV	REVISED
	PLOT SCALE -	CHECKED - AJS	REVISED
	PLOT DATE - 12/14/11	DATE - 12/14/11	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CARPENTER STREET IMPROVEMENTS
SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 3 OF 12 SHEETS STA. TO STA.

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2614	11-00102-00-RS	DU PAGE	12	3
CONTRACT NO. 63673				
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		