

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE RESURFACING 0005 80% FEDERAL 20% LOCAL
20200100	EARTH EXCAVATION	CU YD	10	10
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	260	260
25200100	SODDING	SQ YD	260	260
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,100	4,100
40600300	AGGREGATE (PRIME COAT)	TON	85	85
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1 1/4, 4.75, N50	TON	1,140	1,140
40600895	CONSTRUCTION TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	310	310
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,300	2,300
42101300	PROTECTIVE COAT	SQ YD	430	430
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	40	40
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1,300	1,300
42400800	DETECTABLE WARNINGS	SQ FT	258	258
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	20,400	20,400
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	40	40
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,100	1,100
44000600	SIDEWALK REMOVAL	SQ FT	1,300	1,300
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	205	205
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	410	410

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE RESURFACING 0005 80% FEDERAL 20% LOCAL
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	610	610
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	815	815
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	3	3
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	8	8
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	43	43
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15	15
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15	15
60603800	COMBINATION CURB AND GUTTER TYPE B-6.12	FOOT	1,100	1,100
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5,550	5,550
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	420	420
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,900	11,900
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	180	180
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	150	150
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,225	1,225
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	345	345
X6026624	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	1	1
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	24	24
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L. Sum	1	1

* DENOTES SPECIALTY ITEM

Drawing file: W:\Projects\74011135 - Washington Blvd LAPP\Quantities_2007.dwg Feb 02, 2012 - 8:51am



USER NAME -	DESIGNED - ALA	REVISED -
PLOT SCALE -	DRAWN - MK, DMM	REVISED -
PLOT DATE -	CHECKED - ALA	REVISED -
	DATE - 12-7-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

ROUTE NO. FAU 1411	SECTION 11-0093-00-RS	COUNTY COOK	TOTAL SHEETS 14	SHEET NO. 3
FIELD BOOK NO. -AERIALS/LL		CONTRACT NO. 63686		
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT M-9003(943)		

E.H.E. PROJECT NO. 740-11-15501