

SUMMARY OF QUANTITIES

CODE No.	ITEMS	UNIT	CONSTRUCTION TYPE CODE 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER))	UNIT	215
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	32
20200100	EARTH EXCAVATION	CU YD	576
20900110	POROUS GRANULAR BACKFILL	CU YD	74
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,623
21400100	GRADING AND SHAPING DITCHES	FOOT	1,800
25000210	SEEDING, CLASS 2A	ACRE	0.96
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	104
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	104
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	104
25200110	SODDING, SALT TOLERANT	SQ YD	1,355
25100630	EROSION CONTROL BLANKET	SQ YD	4,623
28000510	INLET FILTERS	EACH	4
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,644
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	159
35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	159
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	13.50
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14,158
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	632

CODE No.	ITEMS	UNIT	CONSTRUCTION TYPE CODE 0021
42400800	DETECTABLE WARNINGS	SQ FT	50
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	228
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	151
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	8
60107600	PIPE UNDERDRAINS 4"	FOOT	105
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L SUM	1
* 72000100	SIGN PANEL - TYPE 1	SQ FT	78
* 72900100	METAL POST - TYPE A	FOOT	81
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	78
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	97
Z0022800	FENCE REMOVAL	FOOT	24
XZ127900	RETAINING WALL REMOVAL	FOOT	7
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	8
50104400	CONCRETE HEADWALL REMOVAL	EACH	2
* Z0033058	POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)	EACH	2
X0322917	Proposed Storm Sewer Connection to existing Manhole	EACH	1

* DENOTES SPECIALTY ITEM

STA. 10+31 TO STA. 26+06 (GERMAN CHURCH ROAD) STA. 10+19 TO STA. 18+32 (SCHOOL STREET) STA. 11+19 TO STA. 17+00 (WOLF ROAD)	DRAWN BY: JMH	REVISED: _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	FAU RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED BY: JCH	REVISED: _____			1552 (G.C.)	11-00032-00-SW	COOK	20	3
	DATE: 04/27/11	REVISED: _____			CONTRACT No. 63688				
	REVISED: 01.10.12	REVISED: _____			SCALE: N.T.S.	SHEET No. 3 OF 20 SHEETS	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

FILE 006 No. 10-810